

N:\land projects\16001\16619\wg\16619004-IMP-00.dwg, PH 3 - IMP 2, 2/17/2020 12:11:22 PM, bnaac, 1:1

R.J.P. = RESTRAINED JOINT PIPE

LENGTH OF PIPE TO BE RESTRAINED IN EACH DIRECTION
FROM CENTERLINE OF BEND, EXCEPT AS NOTED BELOW

DESCRIPTION	8"	10"
90° BEND	58'	72'
45° BEND	24'	30'
22 1/2° BEND	12'	14'
11 1/4° BEND	6'	7'
8" x 6" TEE	41' BRANCH	
10" x 8" TEE	54' BRANCH	

HORIZONTAL

LENGTH OF PIPE TO BE RESTRAINED IN
EACH DIRECTION FROM CENTERLINE OF
BEND, EXCEPT AS NOTED BELOW


DESCRIPTION	8"	10"
11 1/4° UP BEND	6'	7'
11 1/4° DOWN BEND	11'	13'
22 1/2° UP BEND	12'	14'
22 1/2° DOWN BEND	22'	26'
45° UP BEND	24'	30'
45° DOWN BEND	45'	55'
DEAD END	54'	67'

VERTICAL

PIPE RESTRAINTS SCHEDULE FOR JOINTS


NO DRIVEWAY MAY BE PLACED OVER WATER SERVICE.
NO DRIVEWAY MAY BE PLACED OVER SANITARY SEWER MANHOLE.

NOTE:
HIGH WATER TABLES ARE APPARENT IN THIS AREA. IF BASEMENTS
ARE CONSTRUCTED, IT IS THE RESPONSIBILITY OF THE BUILDER TO
TAKE SPECIAL PRECAUTION TO ENSURE THE BASEMENTS STAY DRY.




INTERSECTION DETAIL
WEST MEADOW DRIVE & VANTAGE COURT

SCALE: 1"=30'
ANGLES SHOWN ARE 22.5° UNLESS NOTED OTHERWISE
ELEVATIONS SHOWN TOP OF CURB UNLESS NOTED OTHERWISE



CUL-DE-SAC DETAIL
VANTAGE COURT

SCALE: 1"=30'
ANGLES SHOWN ARE 22.5° UNLESS NOTED OTHERWISE
ELEVATIONS SHOWN TOP OF CURB UNLESS NOTED OTHERWISE



WESTVIEW MEADOWS PHASE 3

SECTION 9, TOWN 3, RANGE 2
WEST CHESTER TOWNSHIP
BUTLER COUNTY, OHIO

IMPROVEMENT PLAN

Date	01/03/20
Scale	AS NOTED
Drawn By	BC
Proj. Mgr.	JW
Survey Database	N/A
DWG	16619004-IMP-00
X-Ref(s)	
Project Number	16619.00
File No.	Sheet No. 2/7

MSP
DESIGN
McGill Smith Punshon

Architecture
Engineering
Landscape Architecture
Planning
Surveying
3700 Park 42 Drive
Suite 1908
Cincinnati OH 45241
Phone 513.759.0004
www.mspdesign.com

Revision	By	Date
BCWS COMMENTS	JW	02/11/20




N:\land projects\166001\16619\dwg\16619004-IMP-00.dwg PH 3 - GRA 3, 2/14/2020 7:49:22 AM, btranc, 1:1



CALL TWO WORKING DAYS BEFORE YOU DIG
(NON MEMBERS MUST BE CALLED DIRECTLY)

LEGEND

- INLET PROTECTION
- GRAVEL DITCH CHECK
- SILT FENCE
- 100 YR FLOOD ROUTE
- EXISTING CONTOUR
- PROPOSED CONTOUR



WESTVIEW MEADOWS PHASE 3

SECTION 9, TOWN 3, RANGE 2
WEST CHESTER TOWNSHIP
BUTLER COUNTY, OHIO

GRADING & S.W.P.P. PLAN

Date	01/03/20
Scale	AS NOTED
Drawn By	BC
Proj. Mgr.	JW
Survey Database	N/A
DWG	16619004-IMP-00
X-Ref(s)	
Project Number	16619.00
File No.	Sheet No. 3 / 7



3700 Park 42 Drive
Suite 1908
Cincinnati OH 45241
Phone 513.759.0004
www.mspdesign.com

GENERAL NPDES NOTES

- PROJECT INVOLVES THE CONSTRUCTION OF ROADS, HOUSES AND UTILITIES FOR A SINGLE FAMILY SUBDIVISION.
- AREA TO BE DISTURBED IS APPROXIMATELY 6 ACRES.
- PRE-CONSTRUCTION RUNOFF COEFFICIENT IS 0.32.
POST-CONSTRUCTION RUNOFF COEFFICIENT IS 0.50.
- PREDOMINATE SOIL TYPES ARE FINCASTLE SILT LOAM & XENIA SILT LOAM.
- THE EAST FORK OF MILL CREEK IS THE FIRST NAMED STREAM RECEIVING RUNOFF FROM THIS SITE.
- NPDES STORM WATER GENERAL PERMIT NUMBER: 1GC06880+AG
- PROJECT DURATION: THRU 2021
- SITE OPERATOR: M/I HOMES OF CINCINNATI, LLC
8349 WATERSTONE BLVD, SUITE 100
CINCINNATI, OH 45249
(513) 248-5400
- SWPPP CONTACT: M/I HOMES OF CINCINNATI, LLC
8349 WATERSTONE BLVD, SUITE 100
CINCINNATI, OH 45249
(513) 248-5400
CONTACT: MIKE ATHAN
- UNLESS OTHERWISE NOTED, STANDARDS AND SPECIFICATIONS ESTABLISHED IN THE LATEST EDITION OF THE OHIO DEPARTMENT OF NATURAL RESOURCES "RAINWATER AND LAND DEVELOPMENT" MANUAL, CURRENT EDITION, SHALL GOVERN THE EROSION AND SEDIMENT CONTROL INSTALLATIONS SPECIFIED ON THIS PLAN.
- THE DEVELOPER AND CONTRACTOR SHALL ABIDE BY THE RULES AND REGULATIONS SET FORTH IN THE OHIO EPA PERMIT NO. OH-CO000005 - "AUTHORIZATION FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY" UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES).
- THE SWP3 PLAN, NOI APPLICATION, AND LETTER GRANTING PERMIT COVERAGE SHALL BE RETAINED ON SITE AT ALL TIMES IN THE PROJECT TRAILER AND SHALL BE MADE AVAILABLE IMMEDIATELY UPON REQUEST OF THE OHIO EPA DIRECTOR OR HIS AUTHORIZED REPRESENTATIVE DURING WORKING HOURS.
- PRIOR TO COMMENCEMENT OF CONSTRUCTION OPERATIONS, ALL SEDIMENTATION AND EROSION CONTROL FEATURES SHALL BE IN PLACE.
- SEDIMENT CONTROL STRUCTURES SHALL BE FUNCTIONAL THROUGHOUT THE COURSE OF EARTH DISTURBING ACTIVITY, AND SHALL CONTINUE TO FUNCTION UNTIL THE UP-SLOPE DEVELOPMENT AREA IS RESTORABLE. CONSTRUCTION PROGRESSES AND THE TOPOGRAPHY IS ALTERED, APPROPRIATE CONTROLS MUST BE CONSTRUCTED OR EXISTING CONTROLS ALTERED TO ADDRESS THE CHANGING DRAINAGE PATTERNS.
- ALL GROUND SURFACE AREAS THAT HAVE BEEN EXPOSED OR LEFT BARE AS A RESULT OF DEMOLITION AND ARE TO REMAIN SO, SHALL BE SEEDING AND MULCHED AS SOON AS PRACTICAL IN ACCORDANCE WITH STATE OF OHIO SPECIFICATION ITEM 659, AND IN ACCORDANCE WITH THE CONDITIONS OF THE NPDES STORM WATER GENERAL PERMIT.

MAINTENANCE OF CONTROLS

- SILT FENCE AND FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND DAILY DURING A PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- SHOULD THE FABRIC ON A FENCE OR FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE AND THE BARRIER IS STILL NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
- SEDIMENT DEPOSITS SHALL BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
- ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE AND PREPARED FOR SEEDING.
- SEDIMENT SHALL BE REMOVED FROM POND AT SUCH TIME WHEN SEDIMENT OCCUPIES 50% OF BASIN DEPTH.

CONSTRUCTION SEQUENCE

- INSTALL EROSION AND SEDIMENT CONTROL MEASURES BEFORE UPSLOPE CLEARING AND GRADING.
- GRADING AND STRIPPING OF THE REMAINING AREAS OF THE DEVELOPMENT SITE OR PROJECT AREA.
- INSTALL STORMWATER MANAGEMENT SYSTEM.
- TEMPORARY VEGETATIVE STABILIZATION OF EROSION AND SEDIMENT CONTROL MEASURES.
- GRADING OF SUBDIVISION STREET.
- INSTALLATION OF ALL UTILITIES.
- SITE CONSTRUCTION.
- FINAL GRADING, STABILIZATION, AND LANDSCAPING.
- REMOVAL OF EROSION AND SEDIMENT CONTROLS MEASURES.

*DUE TO THE DYNAMICS AND STAGING OF EARTH MOVEMENT, CONTRACTOR MAY NEED TO ALTER THE EROSION CONTROL MEASURES AS SHOWN HEREON. CONTRACTOR TO APPLY (B.M.P.) BEST MANAGEMENT PRACTICES IN ORDER TO CONTROL THE RUNOFF OF SILT AND SEDIMENT.







*ADDITIONAL SILT FENCE MAY BE REQUIRED AS SITE CONDITIONS DETERMINE.

*IF A TEMPORARY STOCKPILE IS CREATED, SILT FENCE SHALL BE PLACED AT THE TOE OF SLOPE

ADDITIONAL NOTES

- A DETAILED MAINTENANCE PLAN THAT DESCRIBES PROCEDURES (E.G. INSPECTIONS SEE SECTION 2.18 INSPECTION OF STORM WATER CONTROLS/INTERNAL INSPECTIONS) NEEDED TO ENSURE THE CONTINUED PERFORMANCE OF CONTROL PRACTICES SHALL BE LOCATED AT THE ENTRANCE OF THE DEVELOPMENT AREA OR AT THE JOB TRAILER IN A WELL-MARKED CONTAINER ACCESSIBLE AT ALL TIMES. PLANS MUST ENSURE POLLUTANTS COLLECTED WITHIN STRUCTURAL POST-CONSTRUCTION SUCH PRACTICES, BE DISPOSED OF IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS.
- ESTABLISH VEGETATION ON ALL BARE AREAS AS PER O.E.P.A. N.P.D.E.S. REGULATIONS.
- CONTRACTOR IS RESPONSIBLE FOR N.P.D.E.S. INSPECTIONS DURING CONSTRUCTION PERIOD.
- HIGH WATER TABLES ARE APPARENT IN THIS AREA. IF BASEMENTS ARE CONSTRUCTED, IT IS THE RESPONSIBILITY OF THE BUILDER TO TAKE SPECIAL PRECAUTION TO ENSURE THE BASEMENTS STAY DRY.
- THE TOP FOOT OF LOT FILLS NECESSARY TO ACHIEVE PLAN GRADE MAY CONSIST OF REDISTRIBUTED TOP SOIL.


N:\land projects\1600016619\wg\16619004-IMP-00.dwg, PH 3 - PRO 4, 2/12/2020 12:41:40 PM, bharv, 1:1




WESTVIEW MEADOWS PHASE 3

SECTION 9, TOWN 3, RANGE 2
WEST CHESTER TOWNSHIP
BUTLER COUNTY, OHIO
PROFILES & DETAILS

Date	01/03/20
Scale	AS NOTED
Drawn By	BC
Proj. Mgr.	JW
Survey Database	N/A
DWG	16619004-IMP-00
X-Ref(s)	
Project Number	16619.00
File No.	Sheet No. 4 / 7




SIDE WALK RESTORATION DETAIL




PIPE SIZE	CY CONC PER LIN FT	LENGTH OF NO 3 BARS	SPACING (FT) BETWEEN NO 3 BARS
6"	0.121	3'-9"	1.64
8"	0.138	4'-0"	1.25
10"	0.157	4'-9"	1.12
12"	0.177	5'-3"	1.02
16"	0.250	6'-3"	0.85
18"	0.247	6'-10"	0.78
20"	0.270	7'-5"	0.72
24"	0.315	8'-6"	0.63
30"	0.540	10'-0"	0.57


BCWS STANDARD DETAIL #6240 CONCRETE ENCASEMENT DETAIL



BCWS STANDARD DETAIL #6150 CONNECTION TO EXISTING MANHOLE




BCWS STANDARD DETAIL #6270 TYPICAL TRENCH DETAIL SEWER INSTALLATION




SECTION A - A


M.H. DEPTH	SLAB & DOWELL REINFORCED SQ. IN./FT. E.W.
0'-10"	0.17
1'-10"	0.22
2'-10"	0.27
3'-10"	0.32




SECTION C - C




BCWS STANDARD DETAIL #6280 HOUSE CONNECTION FOR DEEP SEWER




BCWS STANDARD DETAIL #6290 HOUSE CONNECTION FOR SHALLOW SEWER




TYPE "A"




TYPE "B"



TYPE "C"




TYPE "D"




TYPE "E"


BCWS STANDARD DETAIL #4120 PAVEMENT REPLACEMENT DETAILS




BCWS STANDARD DETAIL #6200 STANDARD MANHOLE




BCWS STANDARD DETAIL #6190 DEAD END MANHOLE




BCWS STANDARD DETAIL #6170 ELEVATED MANHOLE DETAIL




BCWS STANDARD DETAIL #5120 SETTING FOR HYDRANT ADJACENT TO MAIN




BCWS STANDARD DETAIL #5270 PERMANENT LAB SAMPLING STATION




BCWS STANDARD DETAIL #5110 TYPICAL FIRE HYDRANT INSTALLATION




BCWS STANDARD DETAIL #5140 DEAD END DETAIL w/ TEMP F.H.




BCWS STANDARD DETAIL #5150 STANDARD INSTALLATION FOR 3/4" AND 1" WATER METER SETTINGS



BCWS STANDARD DETAIL #5280 TYPICAL TRENCH DETAIL WATER MAIN INSTALLATION




BCWS STANDARD DETAIL #5290 MANUAL AIR RELEASE VALVE




BCWS STANDARD DETAIL #5260 PURITY TEST STATION


- THE CARRIER PIPE SHALL BE BRACED WITHIN THE CASING PIPE WITH CASING SPACERS THAT PLACE THE CARRIER PIPE IN A "RESTRAINED" POSITION TO PRECLUDE POSSIBLE FLOATATION WHILE PROVIDING 1/2-1" CLEARANCE BETWEEN THE TOP RUNNERS AND THE CASING PIPE.
- CASING SPACERS SHALL BE INSTALLED WITHIN ONE (1) FOOT OF EACH SIDE OF CARRIER PIPE JOINTS, WITHIN ONE (1) FOOT OF EACH END OF THE CASING PIPE AND ON 6 FOOT CENTERS THEREAFTER.
- THERE SHALL BE TWO (2) RUNNERS ON TOP AND TWO (2) RUNNERS ON BOTTOM OF CASING SPACER FOR CARRIER PIPE DIAMETERS OF 4-12" OR TWO (2) RUNNERS ON TOP AND FOUR (4) RUNNERS ON BOTTOM FOR CARRIER PIPE DIAMETERS OF 14-36".
- AT EACH END OF THE CASING PIPE, THE CARRIER AND CASING PIPE SHALL BE WRAPPED WITH END SEALS.



SECTION A - A



BCWS STANDARD DETAIL #4370 SEWER FORCE MAIN & WATER MAIN ENCASMENT DETAIL



Revision	By	Date
BCWS COMMENTS	JW	02/11/20

WESTVIEW MEADOWS PHASE 3
SECTION 9, TOWN 3, RANGE 2
WEST CHESTER TOWNSHIP
BUTLER COUNTY, OHIO
STANDARD DETAILS

Date	01/03/20
Scale	AS NOTED
Drawn By	BC
Proj. Mgr.	N/A
Survey Database	JW
DWG	16619004-DTL-00
X-Ref(s)	
Project Number	16619.00
File No.	Sheet No. 6 / 7



Architecture Suite 1908
Engineering Cincinnati OH 45241
Landscape Architecture Phone 513.759.0004
Planning
Surveying www.mspdesign.com

Specifications
for
Permanent Seeding

- SITE PREPARATION**
1. A subsoiler, plow or other implement shall be used to reduce soil compaction and allow maximum infiltration. (Maximizing infiltration will help control both runoff rate and water quality.) Subsoiling should be done when the soil moisture is low enough to allow the soil to crack or fracture. Subsoiling shall not be done on slip-prone areas where soil preparation should be limited to what is necessary for establishing vegetation.
 2. The site shall be graded as needed to permit the use of conventional equipment for seeded preparation and seeding.
 3. Resoil shall be applied where needed to establish vegetation.
- SEEDBED PREPARATION**
1. Lime-Agricultural ground limestone shall be applied to acid soil as recommended by a soil test. In lieu of a soil test, lime shall be applied at the rate of 100 lbs./1,000 sq. ft. or 2 tons/ac.
 2. Fertilizer-Fertilizer shall be applied as recommended by a soil test. In lieu of a soil test, fertilizer shall be applied at a rate of 12 lb./1,000 sq. ft. or 500 lb./ac/ of 10-10-10 or 12-12-12 analysis.
 3. The lime and fertilizer shall be worked into the soil with a disk harrow, spring-tooth harrow, or other suitable field implement to a depth of 3 in. On sloping land the soil shall be worked on the contour.
- SEEDING DATES AND SOIL CONDITIONS**
- Seeding should be done March 1 to May 31 or October 1 to September 30. These seeding dates are ideal but, with the use of additional mulch and irrigation, seedings may be made any time throughout the growing season. Tillage/ seeded preparation should be done when the soil is dry enough to crumble and not form ribbons when compressed by hand. For winter seeding, see the following section on dormant seedings.
- DORMANT SEEDINGS**
1. Seedings shall not be planted from October 1 through November 20. During this period the seeds are likely to germinate, but probably will not be able to survive the winter.
 2. The following methods may be used for "Dormant Seeding":
 - From October 1 through November 20, prepare the seedbed, and the required amounts of lime and fertilizer, then mulch and anchor. After November 20, and before March 15, broadcast the selected seed mixture, mulch and anchor. Increase the seeding rates by 50% for this type of seeding.
 - From November 20 through March 15, when soil conditions permit, prepare the seedbed, lime and fertilizer, apply the selected seed mixture, mulch and anchor. Increase the seeding rates by 50% for this type of seeding.
 - Apply seed uniformly with a cyclone seeder, drill, cultipacker seeder, or hydro-seeder (slurry may include seed and fertilizer) on a firm, moist seedbed.
 - Where feasible, except when a cultipacker type seeder is used, the seedbed should be firmed following seeding operations with a cultipacker, roller or light drag. On sloping land, seeding operations should be on the contour where feasible.

- MULCHING**
1. Mulch material shall be applied immediately after seeding. Seedings made during optimum seeding dates and with favorable soil conditions and on very flat areas may not need mulch to achieve adequate stabilization. Dormant seeding shall be mulched.

Permanent Seeding			
Seed Mix	Seeding Rate		Notes:
	lb./ac.	lb./1,000 ft. ²	
General Use			
Creeping Red Fescue	20-40	1/2-1	
Domestic Ryegrass	10-20	1/4-1/2	
Kentucky Bluegrass	10-20	1/4-1/2	
Tall Fescue	40	1	
Dwarf Fescue	40	1	
Steep Banks or Cut Slopes			
Tall Fescue	40	1	
Crown Vetch	10	1/4	Do not seed later than August
Tall Fescue	20	1/2	
Flat Pea	20	1/2	Do not seed later than August
Tall Fescue	20	1/2	
Road Ditches and Swales			
Tall Fescue	40	1	
Dwarf Fescue	90	2 1/4	
Kentucky Bluegrass	5		
Lawns			
Kentucky Bluegrass	60	1 1/2	
Perennial Ryegrass	60	1 1/2	
Kentucky Bluegrass	60	1 1/2	For shaded areas
Creeping Red Fescue	60	1 1/2	
Note: Other approved seed species may be substituted.			

Note: Other approved seed species may be substituted.

Specifications
for
Permanent Seeding

1. Permanent seeding shall not be considered established for at least 1 full year from the time of planting. Seeded areas shall be inspected for failure and reestablished as needed. Depending on site conditions, it may be necessary to irrigate, fertilize, overseed, or reestablish plantings in order to provide permanent vegetation for adequate erosion control.
2. Maintenance fertilization rates shall be established by soil test recommendations or by using the rates shown in the following table.

Mixture	Formula	lb./ac.	lb./1,000 ft. ²	Time	Mowing
Creeping Red Fescue Ryegrass Kentucky Bluegrass	10-10-10	500	12		Not closer than 3"
Tall Fescue	10-10-10	500	12	Fall, yearly or as needed.	Not closer than 4"
Dwarf Fescue	10-10-10	500	12		Not closer than 2"
Crown Vetch Fescue	0-20-20	400	10	Spring, yearly following establishment and every 4-7 yr. thereafter.	Do not mow
Flat Pea Fescue	0-20-20	400	10		Do not mow

Note: Following soil test recommendations is preferred to fertilizer rates shown above.

Specifications
for
Temporary Seeding

Temporary Seeding Species Selection			
Seeding Dates	Species	lb./1,000 ft. ²	Per Ac.
March 1 to August 15	Oats	3	4 bushel
	Tall Fescue	1	40 lb.
	Annual Ryegrass	1	40 lb.
	Perennial Ryegrass	1	40 lb.
August 16 to November 1	Rye	3	2 bushel
	Tall Fescue	1	40 lb.
	Annual Ryegrass	1	40 lb.
	Perennial Ryegrass	1	40 lb.
November 1 to Spring Seeding	Wheat	3	2 bushel
	Tall Fescue	1	40 lb.
	Annual Ryegrass	1	40 lb.
	Perennial Ryegrass	1	40 lb.

Note: Other approved seed species may be substituted.

1. Structural erosion and sediment control practices such as diversions and sediment traps shall be installed and stabilized with temporary seeding prior to grading the rest of the construction site.
 2. Temporary seed shall be applied between construction operations on soil that will not be graded or reworked for 45 days or more. These idle areas should be seeded as soon as possible after grading or shall be seeded within 7 days. Several applications of temporary seeding are necessary on typical construction projects.
 3. The seedbed should be pulverized and loose to ensure the success of establishing vegetation. However, temporary seeding shall not be postponed if ideal seedbed preparation is not possible.
 4. Soil Amendments-Applications of temporary vegetation shall establish adequate stands of vegetation that may require the use of soil amendments. Soil tests should be taken on the site to predict the need for lime and fertilizer.
 5. Seeding Method-Seed shall be applied uniformly with a cyclone seeder, drill, cultipacker seeder, or hydroseeder. When feasible, seed that has been broadcast shall be covered by raking and dragging and then lightly tamped into place using a roller or cultipacker. If hydroseeding is used, the seed and fertilizer will be mixed on site and the seeding shall be done immediately and without interruption.
- MULCHING TEMPORARY SEEDING**
1. Applications of temporary seeding shall include mulch that shall be applied during or immediately after seeding. Seedings made during optimum seeding dates and with favorable soil conditions and on very flat areas may not need mulch to achieve adequate stabilization.
 2. Materials:
 - Straw-If straw is used, it shall be unrattled small-grain straw applied at the rate of 2 tons/ac. or 90 lbs./1,000 sq. ft. (two to three bales). The mulch shall be spread uniformly by hand or mechanically so the soil surface is covered. For uniform distribution of hand-spread mulch, divide area into approximately 1,000 sq. ft. sections and spread two 45-lb. bales of straw in each section.
 - Hydroseders-If wood cellulose fiber is used, it shall be used at 2,000 lb./ac/ or 46 lb./1,000 sq. ft.
 - Other-Other acceptable mulches include mulch matings applied according to manufacturer's recommendations or wood chips applied at 6 tons/ac.
 - Mechanical-A disk, crimper, or similar type tool shall be set straight to punch or anchor the mulch material into the soil. Straw mechanically anchored shall not be finely chopped but, generally, be left longer than 6 in.
 - Mulch Nettings-Netting shall be used according to the manufacturer's recommendations. Netting may be necessary to hold mulch in place in areas of concentrated runoff and on critical slopes.
 - Asphalt Emulsion-Asphalt shall be applied as recommended by the manufacturer or at the rate of 160 gal. /ac.
 - Synthetic Binders-Synthetic binders such as Acrylic DLR (Aqri-Tac), DCA-70, Petroset, Terra Tack or equivalent may be used at rates recommended by manufacturer.
 - Wood Cellulose Fiber-Wood cellulose fiber binder shall be applied at a net dry weight of 750 lb./ac. The wood cellulose fiber shall be mixed with water and the mixture shall contain a maximum of 50 lbs./100 gal.


Specifications
for
Check Dam

- CROSS SECTION**
- Low Center Section Must Cause Flow Over, Not Around, Check Dam
- Positive Slope
- 16" Minimum
- 3" Maximum
- PROFILE**
- 4" - 8" Rock
- Apron
- Flow
1. The check dam shall be constructed of 4-8 in. diameter stone, placed so that it completely covers the width of the channel.
 2. The top of the check dam shall be constructed so that the center is approximately 6 in. lower than the outer edges, so water will flow across the center and not around the ends.
 3. The maximum height of the check dam at the center of the weir shall not exceed 3 ft.
 4. Spacing between dams shall be as shown in the plans or by the following table:


Check Dam Spacing		Channel Slope			
Dam Height (ft.)	< 5%	5 - 10%	10 - 15 %	15 - 20%	
1	65 ft.	30 ft.	20 ft.	15 ft.	
2	130 ft.	65 ft.	40 ft.	30 ft.	
3	200 ft.	100 ft.	65 ft.	50 ft.	

Specifications
for
Mulching

1. Mulch and/or other appropriate vegetative practices shall be applied to disturbed areas within 7 days of grading if the area is to remain dormant (undisturbed) for more than 45 days or on areas and portions of the site which can be brought to final grade.
2. Mulch shall consist of one of the following:
 - Straw-Straw shall be unrattled small-grain straw applied at the rate of 2 tons/ac. or 90 lbs./1,000 sq. ft. (two to three bales). The mulch shall be spread uniformly by hand or mechanically so the soil surface is covered. For uniform distribution of hand-spread mulch, divide area into approximately 1,000 sq. ft. sections and spread two 45-lb. bales of straw in each section.
 - Hydroseders-Wood cellulose fiber should be used at 2,000 lb./ac. or 46 lbs./1,000 sq. ft.
 - Other-Other acceptable mulches include mulch matting applied immediately to manufacturer's recommendations or wood chips applied at 10-20 tons/ac.
 - 3. Mulch Anchoring-Mulch shall be anchored immediately to minimize loss by wind or runoff. The following are accepted methods for anchoring mulch:
 - Mechanical-Use a disk, crimper, or similar type tool set straight to punch or anchor the mulch material into the soil. Straw mechanically anchored shall not be finely chopped but generally be left longer than 6 in.
 - Mulch Nettings-Use according to the manufacturer's recommendations, following all placement and anchoring suggestions. Use in areas of water concentration and steep slopes to hold mulch in place.
 - Asphalt Emulsion-For straw mulch, apply at the rate of 160 gal. /ac. (0.1 gal. /sq) into the mulch as it is being applied or as recommended by the manufacturer.
 - Synthetic Binders-For straw mulch, synthetic binders such as Acrylic DLR (Aqri-Tac), DCA-70, Petroset, Terra Tack or equivalent may be used at rates recommended by manufacturer.
 - Wood Cellulose Fiber-Wood cellulose fiber may be used for anchoring straw. The fiber binder shall be applied at a net dry weight of 750 lb./acre. The wood cellulose fiber shall be mixed with water and the mixture shall contain a maximum of 50 lbs./100 gal.




1. Stone Size-Two-inch stone shall be used, or recycled concrete equivalent.
2. Length-The construction entrance shall be as long as required to stabilize high traffic areas but not less than 50 ft. (except on single residence lot where a 30-ft. minimum length applies).
3. Thickness-The stone layer shall be at least 6 in. thick.
4. Width-The entrance shall be at least 10 ft. wide, but not less than the full width at points where ingress or egress occurs.
5. Bedding-A geotextile shall be placed over the entire area prior to placing stone. It shall have a Grab Tensile Strength of at least 200 lb. and a Mullen Burst Strength of at least 190 lbs.
6. Culvert-A pipe or culvert shall be constructed under the entrance if needed to prevent surface water flowing across the entrance from being directed out onto paved surfaces.
7. Water Bar-A water bar shall be constructed as part of the construction entrance if needed to prevent surface runoff from flowing the length of the construction entrance and out onto paved surfaces.
8. Maintenance-Top dressing of additional stone shall be applied as conditions demand. Mud spilled, dropped, washed or tracked on public roads, or any surface where runoff is not checked by sediment controls, shall be removed immediately. Removal shall be accomplished by scraping or sweeping.
9. Construction entrances shall not be relied upon to remove mud from vehicles and prevent off-site tracking. Vehicles that enter and leave the construction site shall be restricted from muddy areas.


Specifications
for
Curb Inlet Protection

1. Inlet protection shall be constructed either before upslope land disturbance begins or before the storm drain becomes operational.
2. The wooden frame is to be constructed of 2-by-4 in. construction grade lumber. The end spacers shall be a minimum of 1 ft. beyond both ends of the throat opening. The anchors shall be nailed to 2-by-4 in. stakes driven on the opposite side of the curb.
3. The wire mesh shall be of sufficient strength to support fabric and stone. It shall be a continuous piece with a minimum width of 30 in. and 4 ft. longer than the throat length of the inlet, 2 ft. on each side.
4. Geotextile cloth shall have an equivalent opening size (EOS) of 20-40 sieve and be resistant to sunlight. It shall be at least the same size as the wire mesh.
5. The wire mesh and geotextile cloth shall be formed to the concrete gutter and against the face of the curb on both sides of the throat and securely fastened to the 2-by-4 in. frame.
6. Two-inch stone shall be placed over the wire mesh and geotextile in such a manner as to prevent water from entering the inlet under or around the geotextile cloth.

7. The silt fence shall be placed with the stakes on the downslope side of the geotextile and so that 8-in. of cloth are below the ground surface. Excess material shall lie on the bottom of the 6-in. deep trench. The trench shall be backfilled and compacted.
8. The silt fence shall be placed with the stakes on the downslope side of the geotextile and so that 8-in. of cloth are below the ground surface. Excess material shall lie on the bottom of the 6-in. deep trench. The trench shall be backfilled and compacted.
9. Seams between section of silt fence shall be overlapped with the end stakes of each section wrapped together before driving into the ground.

Specifications
for
Inlet Protection in Swales, Ditch Lines or Yard Inlets

1. Inlet protection shall be constructed either before upslope land disturbance begins or before the storm drain becomes operational.
2. The earth around the inlet shall be excavated completely to a depth of at least 18 in.
3. The wooden frame shall be constructed of 2-by-4 in. construction grade lumber. The 2-by-4 in. posts shall be driven 1 ft. into the ground at four corners of the inlet and the top portion of 2-by-4 in. frame assembled using the overlap joint shown. The top of the frame shall be at least 6 in. below adjacent roads if ponded water would pose a safety hazard to traffic.
4. Wire mesh shall be of sufficient strength to support fabric with water fully impounded against it. It shall be stretched tightly around the frame and fastened securely to the frame.
5. Geotextile shall have an equivalent opening size of 20-40 sieve and be resistant to sunlight. It shall be stretched tightly around the frame and fastened securely. It shall extend from the top of the frame to 18 in. below the inlet notch elevation. The geotextile shall overlap across one side of the inlet so the ends of the cloth are not fastened to the same post.
6. Backfill shall be placed around the inlet in compacted 6-in. layers until the earth is even with notch elevation on ends and top elevation on sides.
7. A compacted earth dike or a check dam shall be constructed in the ditch line below the inlet if the inlet is not in a depression and if runoff bypassing the inlet will not flow to a settling pond. The top of the earth dikes shall be at least 6 in. higher than the top of the frame.



1. Silt fence shall be constructed before upslope land disturbance begins.
2. All silt fences shall be placed as close to the contour as possible so that water will not concentrate at low points in the fence and so that small swales or depressions, which may carry small concentrated flows to the silt fence, are dissipated along its length.
3. To prevent water ponded by the silt fence from flowing around the ends, each end shall be constructed upslope so that the ends are at a higher elevation.
4. Where possible, silt fence shall be placed on the flattest area available.
5. Where possible, vegetation shall be preserved for 5 ft. (or as much as possible) upslope from the silt fence. If vegetation is removed, it shall be reestablished within 7 days from the installation of the silt fence.
6. The height of the silt fence shall be a minimum of 16 in. above the original ground surface.
7. The silt fence shall be placed in a trench cut a minimum of 6 in. deep. The trench shall be cut with a trencher, cable laying machine, or other suitable device that will create an adequately uniform trench depth.
8. The silt fence shall be placed with the stakes on the downslope side of the geotextile and so that 8-in. of cloth are below the ground surface. Excess material shall lie on the bottom of the 6-in. deep trench. The trench shall be backfilled and compacted.
9. Seams between section of silt fence shall be overlapped with the end stakes of each section wrapped together before driving into the ground.


5. The height of the slit fence shall be a minimum of 16 in. above the original ground surface.

6. The slit fence shall be placed in a trench cut a minimum of 6 in. deep. The trench shall be cut with a trencher, cable laying machine, or other suitable device that will ensure an adequately uniform trench depth.

7. The slit fence shall be placed with the stakes on the downslope side of the geotextile and so that 8-in. of the geotextile are below the ground surface. Excess material shall lie on the bottom of the 6-in. deep trench. The slit fence shall be backfilled and compacted.

8. Seams between section of slit fence shall be overlapped with the seams of each section wrapped together before driving into the ground.

Fabric Properties	
Minimum Tensile Strength	120 lbs.
Maximum Elongation at 60 lbs	50%
Minimum Puncture Strength	30 lbs
Minimum Tear Strength	40 lbs
Minimum Burst Strength	200 psi
Apparent Opening Size	0.075 mm (No. 200)
Minimum Permeability	1 x 10 ⁻⁶ sec/cm ²
Ultraviolet Exposure Strength Retention	70 %



- CONCRETE WASHOUT DETAIL**
- N.T.S.
- VARIES Depending on Slope Of Existing Ground
- MULCH BERM DETAIL**
- N.T.S.
- DANDY BAG®**
- STORM SEWER GRATE
- LIFT STRAPS USED FOR EASY MOVEMENT AND INSPECTION OF UNIT
- VELCRO CLOSURE
- DANDY BAG®**
- STORM SEWER GRATE
- NOTE: THE DANDY BAG® WILL BE MANUFACTURED IN THE U.S.A. FROM A WOVEN MONOFILAMENT FABRIC THAT MEETS OR EXCEEDS THE FOLLOWING SPECIFICATIONS:
- H-FLOW DANDY BAG® (SAFETY ORANGE)**

Mechanical Properties	Test Method	Units	MARV
Grab Tensile Strength	ASTM D 4632	kN (lbs)	1.62 (365) x 0.89 (200)
Grab Tensile Elongation	ASTM D 4632	%	24 x 10
Puncture Strength	ASTM D 4633	kN (lbs)	0.42 (95)
Mullen Burst Strength	ASTM D 3786	kPa (psi)	3097 (450)
Triplicate Tear Strength	ASTM D 2533	kN (lbs)	0.51 (115) x 0.33 (75)
UV Resistance	ASTM D 4355	%	90
Apparent Opening Size	ASTM D 4751	mm (US Std. Sieve)	0.425 (40)
Flow Rate	ASTM D 4491	l/min/m ² (gal/min/ft ²)	900 (145)
Permeability	ASTM D 4491	Sec-1	2.1

*Note: All Dandy Bags® can be ordered with our optional oil absorbent pillows

- Criteria for Silt Fence Materials**
1. Fence Posts-The length shall be a minimum of 32 in. long. Wood posts will be 2-by-2 in. of hardwood of sound quality. The maximum spacing between posts shall be 10 ft.
 2. Silt Fence Fabric shall be ODOT Type C Geotextile Fabric or as described by the chart below:

OHIO Utilities Protection SERVICE

Call Before You Dig

1-800-362-2764

CALL TWO WORKING DAYS BEFORE YOU DIG (NON MEMBERS MUST BE CALLED DIRECTLY)

STATE OF OHIO

JAMES H. WATSON

49886

REGISTERED PROFESSIONAL ENGINEER

OHIO UTILITIES PROTECTION SERVICE

Call Before You Dig

1-800-362-2764

CALL TWO WORKING DAYS BEFORE YOU DIG (NON MEMBERS MUST BE CALLED DIRECTLY)

Revision

By

Date

Scale

AS NOTED

Drawn By

BC

Proj. Mgr.

JW

Survey Database

N/A

DWG

16619004-DTL-00

X-Ref(s)

Project Number

16619.00

File No.

Sheet No.

7 / 7

WESTVIEW MEADOWS
PHASE 3SECTION 9, TOWN 3, RANGE 2
WEST CHESTER TOWNSHIP
BUTLER COUNTY, OHIO

EROSION CONTROL NOTES & DETAILS

Date

01/03/20

Scale

AS NOTED

Drawn By

BC

Proj. Mgr.

JW

Survey Database

N/A

DWG

16619004-DTL-00

X-Ref(s)

Project Number

16619.00

File No.

Sheet No.

7 / 7

MSP

DESIGN

McGill Smith Punshon

• Architecture

• Engineering

• Landscape Architecture

• Planning

• Surveying

3700 Park 42 Drive

Suite 1908

Cincinnati OH 45241

Phone 513.759.0004

www.mspsdesign.com