

## GENERAL NOTES


- Item numbers refer to the Ohio Department of Transportation construction and material specifications, and all construction work shall be done according to said specifications of Butler County requirements and standards for subdivisions. When in conflict, the County requirements shall prevail.
- Items that pertain to underground utilities such as watermain pipe, sanitary sewer pipe, water valves and manhole frames and covers, etc., will remain under specifications of the utility serving the area. Storm sewers shall be designed and constructed in accordance with the requirements of the Butler County Engineer.
- All trenches within the right-of-way and 10' utility easement shall be compacted and backfilled in accordance with item 204 and 603 (ODOT 2010) in the state specifications.
- Surface course (item 448) and tack coat (item 407) are to be applied no sooner than nine (9) months after the leveling course, (item 448), and fifty (50) percent of the homes are completed. If after two (2) years fifty (50) percent of the homes have not been completed, then the top course may be applied.
- A minimum 10' utility easement shall be shown on the record plat parallel and immediately adjacent to the right-of-way line allowing for installation, operation and maintenance of sewers, water, electric and telephone conduits and any other public or quasi public utility.
- Developer shall be responsible for the installation of conduits for the full width of the public right-of-way at a depth of 36" for use by the electric, telephone and cable services. The location of the lines shall be coordinated with utility companies by the developer.
- All electrical transformers shall be located so that they do not interfere with the existing manholes or water main appurtenances.
- Sump line conduits are to be SDR 35.
- WATER MAIN**
  - Water main materials, valves, fire hydrants, fittings and appurtenances and installation to be as per Butler County specifications, using class 53 Ductile Iron as per AWWA C-151 with minimum 4' cover.
  - All water main valves to have a minimum depth of 2.5' and a maximum depth of 4' from proposed grade to the top of the Valve Operating Nut.
  - Minimum 10' horizontal, 18" vertical separation between water main and sanitary and/or storm sewer.
  - If meter pits cannot be initially installed at the location shown on the typical section, a curb stop can be set up at this location.
- SANITARY SEWER**
  - Sanitary sewer materials and installation to be as per Butler County specifications, using Section 3110 for PVC SDR-35 & 26 pipe; Section 3140 for ABS or PVC composite pipe; Section 3410 for manholes.
  - Crossings Whenever a sanitary sewer and water main must cross, the sewer shall be at such an elevation that the crown of the sewer is at least 18 inches measured between the outside pipe walls, below the bottom of the water main. If it is absolutely impossible to maintain the 18 inch vertical separation, the water main shall be relocated or the sewer shall be constructed as follows:
    - A sewer passing over or under the water main shall be encased or constructed of materials that are equivalent to water main standards of construction for a minimum distance of 10 feet on each side of the water main.
    - The sewer crossing shall be constructed so that the sewer joints will be equidistant and as far as possible from the water main joints.
    - Where a water main passes under a sewer, adequate structural support shall be provided for the sewer to prevent damage to the water main.
  - Sanitary laterals shall be extended to at least ten (10) feet beyond the Property / Right-of-Way or to the edge of the easement, whichever is greater.
  - Sanitary sewer laterals, which shall include all pipe and appurtenances from the building to the public sewer main, and the connection to the public sewer main shall be considered private and the responsibility of the property owner to maintain. The connection to the sewer would be any piping that extends out from the main barrel of the sewer main.
  - All buildings to be served by the public sewer system shall be constructed so as to provide a minimum of four feet (4') of vertical separation between the public sanitary sewer, at the point of connection, and the lowest building level served by a gravity sewer connection and shall not exceed a depth of 12 feet below finish grade at the end of the lateral at the right-of-way unless specifically authorized by the County. In addition, said building level shall be at least one (1) foot above the lowest point of free-overflow (non-sealed manhole cover) upstream of any treatment facility or wastewater pumping facility that receives the discharge from said building. Said minimum service levels shall be recorded on the "As-built" plans for the development which will be kept on file in the office of the Butler County Department of Environmental Services.
- Butler County Water and Sewer Department does not accept any responsibility for the relocation, repair, or replacement of any other utility installed within five (5) feet of the center line of any sanitary sewer main or water main.
- STORM SEWER**
  - Storm sewer pipe shall meet the requirements as follows:
    - PVC pipe as per ODOT Specification 707.42 for all diameters
    - HDPE pipe as per ODOT Specification 707.33
    - Corrugated steel pipe as per ODOT Specification 707.01 or 707.02 for all diameters
    - Reinforced concrete pipe as per ODOT Construction and Material Specification 706.02 for all diameters. Class shall be specified at the contractor's request. (Cincinnati Concrete Pipe, Duracrete or equal).
  - Blumious coated corrugated steel pipe as per ODOT Specification 707.05 or 707.07 Installation shall meet Butler County Specifications. All joints shall be soil seal joints unless specifically noted on the plans
  - Deflection Testing for Storm Sewers and Culverts 15% of all storm sewers shall be tested for deflection within thirty days after they are complete. Butler County Engineer or his designated representative will determine what 15% shall be tested. If any storm sewer in the original 15% is found out of compliance, deflection tests will be required on 100% of the remaining storm sewer. A vertical ring deflection greater than 5% will not be allowed. This deflection is defined as 5% reduction in the vertical base or average inside diameter. The method of testing shall be subject to the approval of the engineer. If rigid balls or mandrels are used to test pipe deflection, no mechanical pulling devices shall be used. The deflection test may be conducted with a nine prong mandrel, a ball or a cylinder or another manner acceptable to the Butler County Engineer or his designated representative. The testing will be accomplished from manhole to manhole or catchbasin to catchbasin, following the complete flushing of the line. The contractor shall furnish all equipment required to complete the deflection testing. The deflection test shall be witnessed by the County Engineer or his designated representative. Any section of pipe that fails to meet the aforementioned requirements shall be rerouted by a procedure acceptable to the County or be excavated and either be relayed or replaced, and retested until the requirements are met.
  - All catch basins and manholes with a depth greater than 4' shall be provided with steps. Steps shall meet the requirements of ODOT STD. 804 and shall conform to the details as shown on Butler County Standard Drawing MH-1A.
  - Headwall: HW-4A to be used with Corrugated Metal pipe or HW-4B to be used with Concrete Pipe.
- Roof drains, foundation drains, and other clean water connections to the sanitary sewer system are prohibited.
- Any detention basin on site should be constructed prior to the clearing of topsoil and grading of the site. All trees and vegetation shall be removed from all proposed detention basins regardless of maintenance responsibility.
- SEDIMENTATION CONTROL**
  - The project has been designed to control erosion and prevent damage to other property. All stripping, earthwork, and regrading shall be performed to minimize erosion. Natural vegetation shall be retained wherever possible. The proposed plan will allow almost all eroded material to be retained on site.
  - All areas disturbed by the construction of the roadways, ditches and sediment basins shall be seeded and strawed as soon as possible to limit the erosion and stabilize the soil. Payment will be by the number of square yards disturbed as per the grading plan. For additional sedimentation control details, see grading plan.
- Butler County will not be responsible for any pavement or storm sewer repairs resulting from water main and sanitary sewer repairs. Butler County also will not be responsible for adjusting manholes, valves, fire hydrants, meter pits, etc. as a result of grade changes. The grantor shall be responsible for proper adjustment of manholes, valves, fire hydrants, meter pits, etc. to the satisfaction of Butler County, due to grade changes, paving, repairing, etc. initiated by the grantor.
- A typical five (5) foot drainage easement is to be provided on both sides of every lot line.
- Any roadway settlement greater than one inch will be required to be repaired with Item 613 Low Strength Mortar Backfill (Type 1). See Detail on Sheet C8.0.
- Provide the Butler County Engineer's Office with a forty-eight (48) hour notice prior to the start of any construction, including sanitary installation. Phone 785-4145.
- Contractors to accept all Quantities as correct prior to beginning construction.
- Contractor shall include the cost of County inspection and extension fees in unit price bid.
- Private driveways, parking lots and other paved areas, earthen berms or structures should not be constructed over private water or sewer service lines within the public road right of way or within the easement areas for the public utilities. Should this occur, the property owner shall be held responsible for the protection and repair and for providing access to any curb stops, meter pits, manholes, clean-outs, etc. installed in conjunction with these private service lines and for any damage or restoration of the paved surfaces or structures that may result from the future operation, maintenance, repair or replacement of said service lines and appurtenances.

# THE OAKS OF WEST CHESTER SECTION FIVE (PHASE EIGHT) FINAL DEVELOPMENT PLAN

## SECTION 22, TOWN 3, RANGE 2 WEST CHESTER TOWNSHIP BUTLER COUNTY, OHIO



- MS610-023-000-014  
Lawrence Gundler Est.  
P.O. Box 401  
West Chester, OH 45071
- MS610-023-000-012  
County of Butler, State of Ohio  
315 High St.  
Hamilton, OH 45011
- MS610-023-000-008  
Anne Subbrook  
7056 Barret Rd.  
West Chester, OH 45069
- MS610-023-000-007  
Earl Gettelberger  
7074 Barret Rd.  
West Chester, OH 45069
- MS610-023-000-008  
James W. Porton Jr.  
7088 Barret Rd.  
West Chester, OH 45069
- MS610-023-000-009  
Hippel & O'Connell  
7118 Barret Rd.  
West Chester, OH 45069
- MS610-023-000-010  
Jeffrey W. & Christine Buchold  
7158 Barret Rd.  
West Chester, OH 45069
- MS610-023-000-006  
Timothy E. & Yvonne C. Poff TR  
7200 Barret Rd.  
West Chester, OH 45069
- MS620-099-000-038  
Kevin A. Meyer & Amanda G. Patten  
7204 Barret Rd.  
West Chester, OH 45069
- MS610-018-000-013  
Trustees of Union Township  
8113 Chidwell Dr.  
West Chester, OH 45069



VICINITY MAP  
NOT TO SCALE

## SECTION FIVE SUMMARY

EXISTING ZONING	R-PUD (7/18/2008)
TYPICAL LOT FRONTAGE	100 FT
SQUARE FOOTAGE (MIN)	15,000 SF
FRONT SETBACK (MIN)	30 FT
SIDE SETBACK (MIN)	5 FT
SIDE SETBACK (TOTAL)	30 FT
(20 FT MIN REQUIRED BTW HOUSES)	
REAR SETBACK	30 FT
NUMBER OF LOTS	8 LOTS
OPEN SPACE LOTS	2 LOTS
TOTAL	10 LOTS
TOTAL ACREAGE	16.665 ACRES
TOTAL OPEN SPACE	10.029 ACRES
% OF OPEN SPACE	60.18%

## PLANNER, ENGINEER, SURVEYOR, AND LANDSCAPE ARCHITECT

BAYER BECKER  
6900 TYLERSVILLE ROAD, SUITE A  
MASON, OHIO 45040  
PH: 513-336-6600

## DEVELOPER

RHEIN GUNDLER LLC  
11025 REED HARTMAN HIGHWAY, SUITE B-1  
CINCINNATI, OH 45242  
PH: 513-891-7100

## OWNERS

ERROL & NANCY GUNDLER  
6466 CONTRERRAS ROAD,  
OXFORD, OH 45056

LAWRENCE & ESTELLA GUNDLER  
6745 BARRETT ROAD  
WEST CHESTER, OH 45071

## BENCHMARK

ON PIN SET - CAPPED BB TRAVERSE LOCATED 12.00'  
WEST OF FIRE HYDRANT AT THE SOUTHWEST  
INTERSECTION OF BARRETT ROAD & SPRUCE HILL CIRCLE  
ELEVATION = 768.52  
ELEVATION BASED ON STATE PLANE COORDINATE  
SYSTEM (NAD 83) OHIO SOUTH ZONE 3402

## INDEX OF SHEETS

DRAWING NO.	DRAWING TITLE	ISSUE DATE	REVISION NO.	REVISION DATE
C1.0	TITLE SHEET	08-13-19	5	11-12-19
C2.0	LAYOUT PLAN	08-13-19	2	10-17-19
C3.0	UTILITY PLAN	08-13-19	4	11-12-19
C4.0	UTILITY PROFILES & DETAILS	08-13-19	6	11-12-19
C5.0	GRADING AND EROSION CONTROL PLAN	08-13-19	4	11-12-19
C5.1	SOIL AND EROSION CONTROL DETAILS	08-13-19		
C6.0	SIGHT DISTANCE EXHIBIT	08-13-19	1	10-10-19
C7.0	BUTLER COUNTY SANITARY DETAILS	08-13-19		
C7.1	BUTLER COUNTY WATER DETAILS	08-13-19		
C7.2	BUTLER COUNTY STORM DETAILS	08-13-19		



LOCATION OF ALL EXISTING UTILITIES TO BE  
DETERMINED IN THE FIELD PRIOR TO CONSTRUCTION

## THE OAKS OF WEST CHESTER SECTION FIVE (PHASE EIGHT) SECTION 22, TOWN 3, RANGE 2 WEST CHESTER TOWNSHIP, BUTLER COUNTY, OHIO

TITLE SHEET

**bayer  
becker**  
www.bayerbecker.com  
6900 Tylersville Road, Suite A  
Mason, OH 45040 - 513.336.6600

Drawing: 06F158-005 CD  
Drawn by: LDF  
Checked by: JSD  
Issue Date: 08-13-19  
Sheet:

C1.0

Item	Revision Description	Date	Chk:	Rev:
1	REVISE PER CLIENT COMMENTS	07-12-19	JSD	
2	REVISED PRIVATE DRIVE LAYOUT, UTILITIES, AND EARTHWORK	10-10-19	CJO	JSD
3	REVISED PER BOWS COMMENTS	10-17-19	CJO	JSD
4	REVISED PER BOWS COMMENTS	11-04-19	CJO	JSD
5	REVISED PER BOWS COMMENTS	11-12-19	CJO	JSD

RECEIVED  
NOV 13 2019

GENERAL NOTES

1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF THE OHIO DEPARTMENT OF TRANSPORTATION (ODOT) "CONSTRUCTION AND MATERIAL SPECIFICATIONS," AND PROJECT SPECIFICATIONS. IN THE EVENT OF A CONFLICT, THE MORE STRINGENT STANDARD APPLIES.
2. WHERE CONNECTING TO EXISTING ASPHALT PAVEMENT, THE CONTRACTOR SHALL SAW CUT THE EXISTING EDGE OF PAVEMENT TO PROVIDE A CLEAN EDGE. ITEM 407 TACK COAT SHALL BE APPLIED TO THE ENTIRE CUT FACE OF THE EXISTING PAVEMENT PRIOR TO THE PLACEMENT OF THE PROPOSED PAVEMENT.
3. TWO (2) AUTUMN BLAZE MAPLE TREES TO BE PLANTED ON EACH LOT BY BUILDER, MINIMUM 2 1/2" CALIPER.

LEGEND

NO TREE CLEARING OR WORK TO BE COMPLETED WITHIN THIS AREA



Know what's below.  
Call before you dig.

LOCATION OF ALL EXISTING UTILITIES TO BE DETERMINED IN THE FIELD PRIOR TO CONSTRUCTION

5.403 Ac.  
O.R. 6971, Pg. 155  
M. Holbrook &  
arnard W. Moffett

5.307 Ac.  
O.R. 6386, Pg. 2314  
Earl G. Gettlefinger

5.282 Ac.  
O.R. 6854, Pg. 765  
Hipolito & Christine Vigil

5.138 Ac.  
D.B. 942, Pg. 727  
Carol K. Buchold

1.15 Ac.  
O.R. 6179, Pg. 1354  
Yvonne C. Poff, Tr., Etal.

5.367 Ac.  
O.R. 5200, Pg. 533  
James W. Parton

OPEN SPACE 124  
9.091 Ac.  
396022 s.f.

OPEN SPACE 125  
0.938 Ac.  
40840 s.f.

119  
0.916 Ac.  
39881 s.f.

120  
0.972 Ac.  
42352 s.f.

121  
1.065 Ac.  
46392 s.f.

122  
1.079 Ac.  
46982 s.f.

123  
1.015 Ac.  
44233 s.f.

86.713 Ac.  
O.R. 7662, Pg. 530  
Lawrence W. Gundler, Etal

Ex. 300' U.E.  
D.B. 784, Pg. 543




Basis of Bearing:  
State Plane NAD83 GPS Observations  
0 50 75  
SCALE: 1" = 50'

THE OAKS OF WEST CHESTER  
SECTION FIVE (PHASE EIGHT)

SECTION 22, TOWN 3, RANGE 2  
WEST CHESTER TOWNSHIP,  
BUTLER COUNTY, OHIO

LAYOUT PLAN



Drawing: 06F158-005 CD  
Drawn by: LDF  
Checked by: JSD  
Issue Date: 08-13-19  
Sheet:

C2.0

UTILITY NOTES:


- 48 hours notice to be given to affected residents before construction begins.
- All Catch Basin T/G Elevations located within the curb are set to the Gutter Line Elevations.
- Lower 1" Water Services as needed to avoid conflicts with Storm with Min. 4' Cover.
- Location of existing utilities to be determined in the field prior to work beginning.
- All lots Sump to Sump Drain unless otherwise noted in plan.
- Sump Lines to be installed as per Standard Service Detail. Wyes or Tees are to be placed ten feet past lot line, on the low side of specified lots, and marked with Wye poles.
- Contractors to accept all quantities as correct prior to beginning construction.
- Contractor end deep connection sanitary sewer laterals at 12" below grade. See detail on sheet C8.0.
- 1" water services to be installed with Type K Copper Pipe.

NOTE:  
MSL = MIN. SERVICE LEVEL - LOWEST FLOOR ELEVATION  
SERVED W/ GRAVITY SANITARY SEWER (8" MAIN INVERT  
AT POINT OF SANITARY LATERAL CONNECTION PLUS 4').

LEGEND



NO TREE CLEARING OR WORK TO BE  
COMPLETED WITHIN THIS AREA




Know what's below.  
Call before you dig.

LOCATION OF ALL EXISTING UTILITIES TO BE  
DETERMINED IN THE FIELD PRIOR TO CONSTRUCTION

Item	Date	Chk	Rev	Rev Description
1	10-10-19	JSD		REVISED PRIVATE DRIVE LAYOUT, UTILITIES, AND EARTHWORK
2	10-17-19	JSD		REVISED PER BOWS COMMENTS
3	11-04-19	JSD		REVISED PER BOWS COMMENTS
4	11-12-19	JSD		REVISED PER BOWS COMMENTS

THE OAKS OF WEST CHESTER  
SECTION FIVE (PHASE EIGHT)  
SECTION 22, TOWN 3, RANGE 2  
WEST CHESTER TOWNSHIP,  
BUTLER COUNTY, OHIO

UTILITY PLAN



Drawing: 06F158-005 CD  
Drawn by: LDF  
Checked by: JSD  
Issue Date: 08-13-19

Sheet:  
**C3.0**



1. LOCATION OF EXISTING UTILITIES TO BE DETERMINED IN THE FIELD PRIOR TO BEGINNING WORK.
2. THE GRADING PLAN IS TO BE USED FOR GRADING PURPOSES ONLY.
3. CONTRACTOR SHALL OBTAIN A COPY OF THE COMPLETE GEOTECHNICAL REPORT PREPARED BY THELEN ASSOCIATES, INC. DATED JANUARY 3, 2007 AND ALL ADDENDUMS PRIOR TO BIDDING THE PROJECT.
4. CONTRACTORS SHALL SET UP AN ONSITE PRE-CONSTRUCTION MEETING WITH THE DEVELOPER, PROJECT GEOTECHNICAL ENGINEER, EARTHWORK CONTRACTOR, AND SITE CIVIL ENGINEER PRIOR TO BEGINNING CONSTRUCTION.
5. CONTRACTOR SHALL ASSUME THE TOP 8" OF EXISTING GROUND IS TOPSOIL. TOPSOIL REMOVED TO DEPTHS GREATER THAN 8" SHALL BE DONE ONLY AFTER CONSULTATION WITH THE PROJECT GEOTECHNICAL ENGINEER AND APPROVAL OF THE DEVELOPER.
6. ALL EARTHWORK AND CONSTRUCTION ACTIVITIES SHALL BE PERFORMED PER THE RECOMMENDATIONS OF THE PROJECT GEOTECHNICAL ENGINEER AS DESCRIBED IN THE GEOTECHNICAL EXPLORATION REPORT AND ALL ADDENDUMS.
7. CONTRACTOR SHALL VERIFY ALL EARTHWORK QUANTITIES PRIOR TO AWARD OF CONTRACT. PAY QUANTITIES ARE FINAL EXCEPT FOR DOCUMENTED UNDERCUT APPROVED BY DEVELOPER PRIOR TO COMPLETION OF THE EARTHWORK. UPON REQUEST, CONTRACTORS MAY HAVE ACCESS TO THE SITE TO FIELD CHECK TOPOGRAPHY.
8. CONTRACTOR TO PROVIDE SILT FENCE AT STORM SEWER OUTLETS (ALONG WITH ROCK CHANNEL PROTECTION AS SPECIFIED ON UTILITY PLAN) TO PREVENT EROSION.
9. CONTRACTOR SHALL INSTALL AND MAINTAIN A CONCRETE WASHOUT FACILITY PER BUTLER COUNTY STANDARDS.
10. EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO CONSTRUCTION AND MAINTAINED DURING CONSTRUCTION.
11. BEST MANAGEMENT PRACTICES (BMPs) SHOWN ON PLANS SHALL BE REVISED OR IMPLEMENTED AS REQUIRED. CONTRACTOR SHALL MONITOR CONSTRUCTION BMPs AND PROVIDE ADDITIONAL BMPs AS REQUIRED TO PREVENT SEDIMENT RUNOFF FROM CONSTRUCTION SITE ONTO PAVEMENT AND NONPAVED AREAS.
12. AT A MINIMUM, ALL EROSION AND SEDIMENT CONTROLS ON THE SITE SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN ONE-HALF INCH OF RAIN PER 24 HOUR PERIOD. QUALIFIED INSPECTION PERSONNEL (THOSE WITH KNOWLEDGE AND EXPERIENCE IN THE INSTALLATION AND MAINTENANCE OF SEDIMENT AND EROSION CONTROLS) SHALL CONDUCT THESE INSPECTIONS TO ENSURE THAT THE CONSTRUCTION PRACTICES ARE ADEQUATE AND EVALUATE WHETHER THE EROSION CONTROL IS ADEQUATE AND PROPERLY IMPLEMENTED OR WHETHER ADDITIONAL CONTROL MEASURES ARE REQUIRED. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED TO ENSURE THAT THE AREAS OPERATING CORRECTLY. DISCHARGE LOCATIONS SHALL BE INSPECTED TO ASCERTAIN WHETHER THE EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO THE RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF-SITE VEHICLE TRACKING.
13. SITE STABILIZATION SHALL BEGIN WITHIN 7 DAYS ON AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED FOR 14 DAYS.
14. ALL MUD OR DEBRIS TRACKED ON EXISTING STREETS SHALL BE CLEANED AT THE END OF EACH DAY OR AS DIRECTED BY BUTLER COUNTY OR THE OWNER. PERIODIC STREET SWEEPING MAY BE REQUIRED.
15. IN ADDITION TO ANY TEMPORARY EROSION, MUD, AND DEBRIS CONTROL DETAILS AND NOTES SHOWN ON THE PLANS, THE CONTRACTOR SHOULD PLACE TEMPORARY OR PERMANENT SEEDING, MULCH, AND/OR EROSION CONTROL MATS OR OTHER GENUINELY ACCEPTED MEASURES TO PREVENT EROSION, MUD, AND DEBRIS FROM BEING DEPOSITED ON OTHER PROPERTY, ON NEWLY CONSTRUCTED OR EXISTING ROADS, OR INTO EXISTING SEWERS OR NEW SEWERS WITHIN THE DEVELOPMENT. THE CONTRACTOR SHOULD CONTINUALLY MONITOR THE CONSTRUCTION PROGRESS AND MAKE ANY NECESSARY TEMPORARY ADJUSTMENTS TO MAINTAIN THIS CONTROL. AFTER THE VEGETATION BECOMES WELL ESTABLISHED, TEMPORARY EROSION AND SEDIMENT CONTROLS CAN BE REMOVED.
16. THE LAST 18" OF FILL OUTSIDE OF PAVEMENT AREAS IS TO BE MADE USING TOPSOIL.

1. CONTRACTOR TO PROVIDE SILT FENCE AT STORM SEWER OUTLETS (ALONG WITH ROCK CHANNEL PROTECTION AS SPECIFIED ON UTILITY PLAN) TO PREVENT EROSION.
2. EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO CONSTRUCTION AND MAINTAINED DURING CONSTRUCTION.
3. BEST MANAGEMENT PRACTICES (BMPs) SHOWN ON PLANS SHALL BE REVISED OR IMPLEMENTED AS REQUIRED. CONTRACTOR SHALL MONITOR CONSTRUCTION BMPs AND PROVIDE ADDITIONAL BMPs AS REQUIRED TO PREVENT SEDIMENT RUNOFF FROM CONSTRUCTION SITE ONTO PAVEMENT AND NON-WORK AREAS.
4. AT A MINIMUM, ALL EROSION AND SEDIMENT CONTROLS ON THE SITE SHALL BE INSPECTED AT LEAST EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN ONE-HALF INCH OF RAIN PER 24 HOUR PERIOD. QUALIFIED INSPECTION PERSONNEL (THOSE WITH KNOWLEDGE AND EXPERIENCE IN THE INSTALLATION AND MAINTENANCE OF SEDIMENT AND EROSION CONTROLS) SHALL CONDUCT THESE INSPECTIONS TO ENSURE THAT THE CONTROL PRACTICES ARE FUNCTIONAL AND TO EVALUATE WHETHER THE EROSION CONTROL IS FUNCTIONAL AND PROTECTING THE ADJACENT ROAD AND LAND. WHEN INSPECTIONS REVEAL REQUIRED, DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. DISCHARGE LOCATIONS SHALL BE INSPECTED TO ASSURE THAT THEY ARE NOT CAUSING OR HAVE THE POTENTIAL TO CAUSE ANY EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO THE RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF-SITE VEHICLE TRACKING.
5. SITE STABILIZATION SHALL BEGIN WITHIN 7 DAYS ON AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED FOR 14 DAYS.
6. ALL MUD OR DEBRIS TRACKED ON EXISTING STREETS SHALL BE CLEANED AT THE END OF EACH DAY OR AS DIRECTED BY WARREN COUNTY OR THE OWNER. PERIODIC STREET SWEEPING MAY BE REQUIRED.
7. IN ADDITION TO ANY EROSION, EROSION, MUD, AND DEBRIS CONTROL DETAILS AND NOTES PROVIDED BY THE PLANNING CONTRACTOR SHOULD PLACE TEMPORARY OR PERMANENT SEEDING, MULCHING AND/OR MULCH NETTING OR ANY OTHER GENERALLY ACCEPTED METHODS TO PREVENT EROSION, MUD, AND DEBRIS FROM BEING DEPOSITED ON OTHER PROPERTY, ON NEWLY CONSTRUCTED OR EXISTING ROADS, OR INTO EXISTING SEWERS OR NEW SEWERS WITHIN THE DEVELOPMENT. THE CONTRACTOR SHOULD CONTINUALLY MONITOR THE CONSTRUCTION PROGRESS AND MAKE NECESSARY TEMPORARY ADJUSTMENTS TO MAINTAIN THIS CONTROL.
8. AFTER THE VEGETATION HAS BECOME WELL ESTABLISHED, TEMPORARY EROSION AND SEDIMENT CONTROLS CAN BE REMOVED.


1. THE CONSTRUCTION ACTIVITY WILL CONSIST OF MASS EARTHWORK, UTILITY INSTALLATION, CURB AND PAVEMENT CONSTRUCTION, AND HOME BUILDING FOR A RESIDENTIAL DEVELOPMENT.
2. ACREAGE:

SECTION FIVE	16.665 ACRES
DISTURBED AREA	2.067 ACRES (MASS EARTHWORK FOR SECTION FIVE DEVELOPMENT)
3. PRIOR LAND USE: WOODS
4. IMPERVIOUS CALCULATIONS:



IMPERVIOUS AREA	
PRE-DEVELOPED	0.0 ACRES
POST-DEVELOPED	0.21 ACRES (SECTION FIVE ONLY)
IMPERVIOUS PERCENTAGE	
PRE-DEVELOPED	0.0 %
POST-DEVELOPED	10 % (SECTION FIVE ONLY)
5. EXISTING SOIL DATA:

<u>SYMBOL</u>	<u>SOIL NAME</u>	
EGE2	EDEN SILTY CLAY LOAM, 15 TO 25% SLOPES MODERATELY ERODED	HSQ
WYB	WYNN SILT LOAM, 2 TO 6% SLOPES	D
WYC2	WYNN SILT LOAM, 6 TO 12% SLOPES MODERATELY ERODED	C
6. POSSIBLE PREVIOUS CONTAMINATIONS: FERTILIZER AND CHEMICALS TO CONTROL WEEDS.
7. SECTION FOUR DRAINS TO WEST PROPERTY LINE AND THEN SOUTHWEST INTO THE BASIN.
8. RUNOFF COEFFICIENT:



PRE-CONSTRUCTION	0.30
POST-CONSTRUCTION	0.50
9. OHIO EPA NPDES PERMIT NUMBER:



### TYPICAL SKIMMER DEWATERING DEVICE




	SEEDING & MULCHING
	DITCH CHECK
	SILT FENCE OR MULCH BERM -----
	DANDY BAG/CURB (OR APPROVED EQUAL)
	GEOTEXTILE INLET PROTECTION
	SEDIMENT TRAP
	CONSTRUCTION ENTRANCE
	CONCRETE WASHOUT
MFOE	MINIMUM FRONT OPENING ELEVATION
	NO TREE CLEARING OR WORK TO BE COMPLETED WITHIN THIS AREA



Item	Revision Description	Date	Drawn: Chk:
1	REVISED PER CLIENT COMMENTS	07-12-19	JSD
2	REVISED PRIVATE DRIVE LAYOUT, UTILITIES AND EARTHWORK	10-10-19	CJO JSD
3	REVISED PER BOWS COMMENTS	10-17-19	CJO JSD
4	REVISED PER BCEO COMMENTS	10-12-19	CJO JSD
5			
6			
7			
8			
9			

**THE OAKS OF WEST CHESTER  
SECTION FIVE (PHASE EIGHT)**  
SECTION 22, TOWN 3, RANGE 2  
WEST CHESTER TOWNSHIP,  
BUTLER COUNTY, OHIO

## GRADING AND EROSION CONTROL PLAN



Drawing:	06F158-005 CD
Drawn by:	LDF
Checked By:	JSD
Issue Date:	08-13-19
Sheet:	

## C5.0

## GENERAL NOTES

### EROSION AND SEDIMENT CONTROLS

#### Vegetative practices

Such practices may include: temporary seeding, permanent seeding, mulching, matting, soil stabilization, vegetative buffer strips, phasing and protection of trees. The contractor shall initiate appropriate vegetative practices on all disturbed areas within seven (7) days if they are to remain dormant (undisturbed) for more than fourteen (14) days. Permanent or temporary soil stabilization shall be applied to disturbed areas within seven (7) days after final grade is reached on any portion of the site.

#### Structural Practices

Structural practices shall be used to control erosion and top sediment from all sites remaining disturbed for more than fourteen (14) days.

#### Timing

Sediment control structures shall be functional throughout earth disturbing activity. Sediment ponds and perimeter sediment barriers shall be implemented as the first step of grading and within seven days from the start of grubbing. They shall continue to function until the upslope development area is restabilized.

#### Sediment Barriers

Sheet flow runoff from denuded areas shall be intercepted by sediment barriers. Sediment barriers, such as sediment fences or diversions direction runoff to settling facilities, shall protect adjacent properties and water resources from sediment transported by sheet flow.


Erosion and sediment control practices used to satisfy the conditions of this plan shall meet the standards and specifications in the current edition of Water Management and Sediment Control in Urbanized Areas (Soil Conservation Service.)

#### Waste Disposal

No solid or liquid waste, including building materials, shall be discharged in storm water runoff. Off-site vehicle tracking of sediments shall be minimized. The plan shall ensure and demonstrate compliance and applicable State of local waste disposal, sanitary sewer or septic system regulations.

#### Maintenance


All temporary and permanent control practices shall be maintained and repaired as needed to assure continued performance of their intended function. The contractor shall be responsible for the maintenance described above.



NOTE: THE DANDY CURB™ WILL BE MANUFACTURED IN THE U.S.A. FROM A WOVEN MONOFILAMENT FABRIC THAT MEETS OR EXCEEDS THE FOLLOWING SPECIFICATIONS:

DANDY CURB™ (SAFETY ORANGE)	Test Method	Units	MARV
Grab Tensile Strength	ASTM D 4832	lbf (lbs)	1.62 (365) X 0.89 (200)
Grab Tensile Elongation	ASTM D 4832	%	2.4 (10)
Puncture Strength	ASTM D 4832	lbf (lbs)	0.40 (90)
Mullen Burst Strength	ASTM D 3788	kPa (psi)	2067 (450)
Trapezoid Tear Strength	ASTM D 4533	lbf (lbs)	0.51 (115) X 0.33 (75)
UV Resistance	ASTM D 4355	%	90
Apparent Opening Size	ASTM D 4751	mm (US Std Sieve)	0.425 (40)
Flow Rate	ASTM D 4481	1/min/m <sup>2</sup> (gal/min/ft <sup>2</sup> )	5907 (145)
Permeability	ASTM D 4481	sec	2.1

\*Note: All Dandy Curb™ can be ordered with our optional oil absorbents





This method of inlet protection is applicable at curb inlets where an overflow capability is necessary to prevent excessive ponding in front of the structure.

#### 14 BLOCK AND GRAVEL CURB INLET SEDIMENT FILTER


### 8 DANDY BAG® Installation and Maintenance Guidelines

**Installation:** The empty Dandy Bag® should be placed over the grate as the grate stands on end. If using optional oil absorbents, place absorbent pillow in pouch, on the bottom (below-grade side) of the unit. Attach absorbent pillow to tether loop. Tuck the enclosure flap inside to completely enclose the grate. Holding the lifting devices (do not rely on lifting devices to support the entire weight of the grate), place the grate into its frame.

**Maintenance:** Remove all accumulated sediment and debris from surface and vicinity of unit after each storm event. Remove sediment that has accumulated within the containment area of the Dandy Bag® as needed. If using optional oil absorbents, remove and replace absorbent pillow when near saturation.





Source: Adapted from product literature of Bekaert Gabions.




This method of inlet protection is applicable where heavy flows are expected and where an overflow capacity is necessary to prevent excessive ponding around the structure.

#### 9 BLOCK AND DROP INLET SEDIMENT FILTER



#### 7 TEMPORARY STREAM CROSSING



#### 11 GEOTEXTILE INLET PROTECTION


##### SPECIFICATIONS FOR INLET PROTECTION IN SWALES, DITCH LINES OR YARD INLETS

- Inlet protection shall be constructed either before upslope land disturbance begins or before the storm drain becomes operational.
- The earth around the inlet shall be excavated completely to a depth of at least 18 in.
- The wooden frame shall be constructed of 2-by-4-in construction-grade lumber. The 2-by-4-in posts shall be driven 1 ft into the ground at four corner of the inlet and the top portion of 2-by-4-in frame assembled using the overlap joint shown. The top of the frame shall be at least 6 in below adjacent roads if ponded water would pose a safety hazard to traffic.
- Wire mesh shall be of sufficient strength to support fabric with water fully impounded against it. It shall be stretched tightly around the frame and fastened securely to the frame.
- Geotextile shall have an equivalent opening size of 20-40 sieve and be resistant to sunlight. It shall be stretched tightly around the frame and fastened securely. It shall extend from the top of the frame to 18 in below the inlet channel. The geotextile shall overlap across one side of the inlet so the ends of the cloth are not fastened to the same post.
- Backfill shall be placed around the inlet in compacted 6-in layers until the earth is even with notch elevation on ends and top elevation on sides.
- A compacted earth dike or a check dam shall be constructed in the ditch line below the inlet if the inlet is not in a depression and if runoff bypassing the inlet will not flow to a settling pond. The top of earth dikes shall be at least 6 in higher than the top of the frame.

INLET PROTECTION - PAGE 125

Source: Rainwater and Land Development, Ohio's Standards for Stormwater Management, Land Development, and Urban Stream Protection. Second Edition-1996

## EROSION CONTROL FOR SMALL SITES




**WARNING!** Extra measures may be needed if your site:

- Is within 300 feet of a stream or wetland
- Is within 1000 feet of a lake
- Is steep (slopes of 12% or more)
- Receives runoff from 10,000 sq. ft. or more of adjacent land
- Has more than an acre of disturbed ground

#### Typical Lawn Seed Mixtures


Grass	Sunny Site	Shady Site
Kentucky bluegrass	65%	15%
Fine fescue	20%	70%
Perennial ryegrass	15%	15%
Seeding rate (lb./1000 sq. ft.)	3-4	4-5

### 7 ROCK CHECK DAM




- The check dam shall be constructed of 4-8 inch diameter stone, placed so that it completely covers the width of the channel. ODOT Type D stone is acceptable, but should be underlain with a gravel filter consisting of ODOT No. 3 or 4 or suitable filter fabric.
- Maximum height of check dam shall not exceed 3.0 feet.
- The midpoint of the rock check dam shall be a minimum of 6 inches lower than the sides in order to direct across the center and away from the channel sides.
- The base of the check dam shall be entrenched approximately 6 inches.
- Spacing of check dams shall be in a manner such that the toe of the upstream dam is at the same elevation as the top of the downstream dam.
- A Splash Apron shall be constructed where check dams are expected to be in use for an extended period of time, a stone apron shall be constructed immediately downstream of the check dam to prevent flows from undercutting the structure. The apron should be 6 in. thick and its length two times the height of the dam.
- Stone placement shall be performed either by hand or mechanically as long as the center of check dam is lower than the sides and extends across entire channel.
- Side slopes shall be a minimum of 2:1.

### 5 SILT FENCE DETAILS




Source: Installation of Straw and Fabric Filter Barriers for Sediment Control, Sherwood and Wyant




Source: Adapted from Installation of Straw and Fabric Filter Barriers for Sediment Control, Sherwood and Wyant

### 12 SOD DROP INLET SEDIMENT FILTER



Source: Adapted from Installation of Straw and Fabric Filter Barriers for Sediment Control, Sherwood and Wyant

### 4 DITCH CHECK



Source: Adapted from Installation of Straw and Fabric Filter Barriers for Sediment Control, Sherwood and Wyant

**REVEGETATION**  
Seed, sod or mulch bare soil as soon as possible  
**SEEDING AND MULCHING**  
Spread 4 to 6 inches of topsoil. Fertilize according to soil test (or apply 10 lb./1000 sq. ft. of 20-10-10 or 10-10-10 fertilizer.) Seed with an appropriate mix for the site (see table.) Rake lightly to cover seed with 1/4" of soil. Roll lightly. Mulch with straw (70-90 lb. or one bale per 1000 sq. ft.) Anchor mulch by punching 2 inches into the soil with a dull, weighted disk or by using netting or other measures on steep slopes, or windy areas. Water gently every day or two to keep soil moist. Less watering is needed once grass is 2 inches tall.

**SODDING**  
Spread 4 to 6 inches of topsoil. Fertilize according to soil test (or apply 10 lb./1000 sq. ft. of 20-10-10 or 10-10-10 fertilizer.) Lightly water the soil. Lay sod. Tamp or roll lightly. On slopes, lay sod starting at the bottom and work toward the top. Peg each piece down in several places. Initial watering should wet soil 6 inches deep (or until water stands 1 inch deep in a straight-sided container.) Then water lightly every day or two for 2 weeks. If construction is completed after October 31, seeding or sodding may be delayed. Applying mulch or temporary seed (such as rye or winter wheat) is recommended if weather permits. Straw bale or silt fences must be maintained until final seeding or sodding is completed in spring March 15- May 31.


**PRESERVING EXISTING VEGETATION**  
Wherever possible, preserve existing trees, shrubs, and other vegetation. To prevent root damage, do not grade, place soil piles, or park vehicles near trees marked for preservation. Place plastic mesh or snow fence barriers around trees to protect the area below their branches.

**STRAW BALE, SILT FENCE OR MULCH BERM**  
Put up before any other work is done. Install on downslope side(s) of site with ends extended up sideslopes a short distance. Place parallel to the contour of the land to allow water to pond behind fence. Entrench 4 inches deep (see back page.) Stake (2 stakes per bale OR 1 stake every 3 feet for silt fence.) Leave no gaps between bales or sections of silt fence. Inspect and repair once a week and after every 1/2 inch rain. Remove sediment if deposits reach half the fence or straw bale height. Maintain until a lawn is established.

**SOIL PILES**  
Located away from any downslope street, driveway, stream, lake, wetland, ditch or drainageway. Temporary seed such as annual rye is recommended for topsoil piles. Surround with straw bales or silt fence.

**GRAVEL DRIVE**  
Install a single access drive using 3 to 5 inch aggregate over a geotextile material. Lay gravel 6 inches deep and 10 feet wide from the foundation to the street. Use to prevent tracking dirt onto the road by all vehicles. Maintain throughout construction until driveway is paved. Park all construction vehicles on the street and off of the site.


**SEDIMENT CLEANUP**  
By the end of each work day, sweep or scrape up soil tracked onto the road. By the end of the next work day after a storm, clean up soil washed off-site, and check straw bales and silt fence for damage or sediment buildup.  
**DOWNSPOUT EXTENDERS**  
Not required, but highly recommended. Install as soon as gutters and downspouts are completed. Route water to a grassed or paved area. Maintain until a lawn is established.



- Stone Size - Two-inch stone shall be used, or recycled concrete equivalent.
- Length - The construction entrance shall be as long as required to stabilize high traffic areas but not less than 70 ft. (except on single residence lots where a 50-ft. minimum length applies).
- Thickness - The stone layer shall be at least 6 in. thick.
- Width - The entrance shall be at least 25 ft. wide, (10 ft. wide for access to individual house lots) but not less than the full width at points where ingress or egress occurs.
- Bedding - A geotextile shall be placed over the entire area prior to placing stone. It shall have a Grab-Tensile Strength of at least 200 lb. and a Mullen Burst Strength of at least 180 lb.
- Culvert - A pipe or culvert shall be constructed under the entrance if needed to prevent surface water flowing across the entrance from being directed out onto paved surfaces.
- Water Bar - A water bar shall be constructed as part of the construction entrance if needed to prevent surface runoff from flowing the length of the construction entrance and soil onto paved surfaces.
- Maintenance - Top dressing of additional stone shall be applied as conditions demand. Mud spilled, dropped, washed or tracked onto public roads, or any surface where runoff is not checked by sediment control, shall be removed immediately. Removal shall be accomplished by scraping or sweeping.
- Construction entrances shall not be relied upon to remove mud from vehicles and prevent off-site tracking. Vehicles that enter and leave the construction site shall be restricted from muddy areas.

#### 21 CONSTRUCTION ENTRANCE

## THE OAKS OF WEST CHESTER SECTION FIVE (PHASE EIGHT) SECTION 22, TOWN 3, RANGE 2 WEST CHESTER TOWNSHIP, BUTLER COUNTY, OHIO







www.bayerbecker.com  
6800 Myersville Road, Suite A  
Mason, OH 45040 - 513.336.0600

Drawing: 06F158-005 CD  
Drawn by: LDF  
Checked by: JSD  
Issue Date: 08-13-19  
Sheet:

C5.1










PIPE SIZE	CY CONC PER LIN FT	LENGTH OF NO. 3 BARS	SPACING (FT) BETWEEN NO. 3 BARS
6"	0.121	3'-9"	1.64
8"	0.139	4'-3"	1.25
10"	0.157	4'-9"	1.12
12"	0.177	5'-3"	1.02
16"	0.200	6'-3"	0.85
18"	0.247	6'-10"	0.78
20"	0.270	7'-5"	0.72
24"	0.315	8'-9"	0.63
30"	0.540	10'-0"	0.57


## CONCRETE ENCASEMENT DETAIL

6240

## DEAD END MANHOLE DETAIL



6120






PIPE SIZE	C.Y. CONC. PER LIN. FT.	LENGTH OF NO. 3 BARS	SPACING (FT) BETWEEN NO. 3 BARS
6"	0.121	3'-9"	1.64
8"	0.139	4'-3"	1.25
10"	0.157	4'-9"	1.12
12"	0.177	5'-3"	1.02
16"	0.200	6'-3"	0.85
18"	0.247	6'-10"	0.78
20"	0.270	7'-5"	0.72
24"	0.315	8'-6"	0.63
30"	0.540	10'-0"	0.57

CONCRETE ENCASEMENT




CONCRETE ROADWAY PAVEMENT REPLACEMENT DETAILS




DEAD END DETAIL WITH TEMPORARY FIRE HYDRANT

5140



TYPICAL CREEK CROSSING & TRENCH DETAIL FOR WATER & SEWER FORCE MAINS


4170



- NOTE:
- 1) PIPE LESS THAN OR EQUAL TO 12" MUST USE 3/4" CORP. STOP, ANGLE BALL VALVE AND SERVICE PIPE.
  - 2) PIPE GREATER THAN 12" TO USE 1" CORP. STOP, ANGLE BALL VALVE AND SERVICE PIPE.


AIR RELEASE VALVE DETAIL

5290




TYPICAL TRENCH DETAIL WATER MAIN INSTALLATION

5280




PERMANENT LAB SAMPLING STATION

5270




TEMPORARY PURITY TEST STATION

5260




STANDARD INSTALLATION FOR 1-1/2" & 2" WATER METER SETTINGS

5170




STANDARD INSTALLATION FOR 3/4" AND 1" WATER METER SETTINGS

5150



SETTING FOR HYDRANT ADJACENT TO MAIN

5120



- NOTE:
- 1) VERIFY LOCATION OF F.H. RELATIVE TO WATER MAIN ON PLANS.
  - 2) CHECK STREET DETAILS FOR RELATIONSHIP BETWEEN MAIN, STREET AND F.H.

TYPICAL FIRE HYDRANT INSTALLATION

5110

THE OAKS OF WEST CHESTER SECTION FIVE

SECTION 22, TOWN 3, RANGE 2  
WEST CHESTER TOWNSHIP,  
BUTLER COUNTY, OHIO

BUTLER COUNTY WATER DETAILS

bayer becker  
www.bayerbecker.com  
6800 Tylerville Road, Suite A  
Mason, OH 45040 - 513.338.6600

Drawing: 06F158-005 CD  
Drawn by: LDF  
Checked by: JSD  
Issue Date: 08-13-19  
Sheet: C7.1

