

A CULVERT DESIGN STUDY
FOR
GENEVA COMPANY

FOR
ACCESS TO PT. LOT 18
DUES SUBDIVISION

UNION TOWNSHIP
BUTLER COUNTY, OHIO

A

CULVERT DESIGN STUDY
FOR
GENEVA INVESTMENT CO.

1/20/94

SUBMITTED BY :

DAN E. ANTENEN
OHIO REG. ENGR. #21804

Dan E. Antenen

1/20/94

GENEVA ACCESS CULVERT STUDY

EXHIBIT A — PROPERTY LOCATION

EXHIBIT B — GENEVA ACCESS CULVERT LOCATION

EXHIBIT C — DRAINAGE AREA

C-1 — Location

C-2 — Sub-area divisions

C-3 — Location of major tributary points
and significant culverts.

C-4 — Elevations & sizes of ex'g culverts

EXHIBIT D — TOTAL DISCHARGE BY TAB. HYDROGRAPH METH

(Computer Sheets) — Sub-area selection and summary —
— T_c & T_t thru Sub-area Computation —
— Sub-area contrib'n & total dischg at outlet

EXHIBIT E — CULVERT SELECTION FOR SITE "C"

E-1 — Comparison of existing culvert capacities

E-2 — Estimates of stream high water flow slope
and allowable head losses.


E-3 — Flows moderated by ex'g conditions

E-4 — Selection of proposed Geneva Access culvert.


EXHIBIT () (SPECIFICATION SHEET) not provided


() (CONSTRUCTION DETAILS) not provided

C/O DAN E. ANTENEN
GENEVA COMPANY IS 1391 NEW LONDON RD.
HAMILTON, OH, 45013
tel. 868-1288



N ←





--- PLOTTED FROM SURVEY NOTES OF 11/28/93 AND 12/22/93 @ = WATER LEVEL (ELEVATIONS) (STRUCTURES)

Project : GENEVA ACCESS

County : Butler

Subtitle: Culvert Study

Subarea : 1

User: DAN

State: OH

Checked: _____

Date: 01-15-94

Date: _____

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			
OTHER AGRICULTURAL LANDS				
Woods	good	- .13(55)	-	-

Total Area (by Hydrologic Soil Group)

.13

====

SUBAREA: 1

TOTAL DRAINAGE AREA: .13 Sq miles

WEIGHTED CURVE NUMBER:55

EXHIBIT D

BATCH OF COMPUTER SHEETS

Project : GENEVA ACCESS

County : Butler

Subtitle: Culvert Study

Subarea : 2

User: DAN

State: OH

Checked: _____

Date: 01-15-94

Date: _____

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			
OTHER AGRICULTURAL LANDS				
Brush - brush, weed, grass mix good	-	.07(48)	-	-

Total Area (by Hydrologic Soil Group)

.07

====

SUBAREA: 2 TOTAL DRAINAGE AREA: .07 Sq miles WEIGHTED CURVE NUMBER:48

t : GENEVA ACCESS User: DAN Date: 01-15-94
 County : Butler State: OH Checked: Date:
 Subtitle: Culvert Study
 Subarea : 3

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			

FULLY DEVELOPED URBAN AREAS (Veg Estab.)				
Open space (Lawns, parks etc.)				
Good condition; grass cover > 75%	-	.09(61)	-	-
Impervious Areas				
Paved parking lots, roofs, driveways	-	.03(98)	-	-
Total Area (by Hydrologic Soil Group)		.12		
		====		

 SUBAREA: 3 TOTAL DRAINAGE AREA: .12 Sq miles WEIGHTED CURVE NUMBER:70

t : GENEVA ACCESS User: DAN Date: 01-15-94
 County : Butler State: OH Checked: Date:
 Subtitle: Culvert Study
 Subarea : 4

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			

FULLY DEVELOPED URBAN AREAS (Veg Estab.)				
Urban Districts	Avg % imperv			
Commercial & business	85	-	.04(92)	-

Total Area (by Hydrologic Soil Group) .04
 =====

SUBAREA: 4 TOTAL DRAINAGE AREA: .04 Sq miles WEIGHTED CURVE NUMBER:92

t : GENEVA ACCESS

County : ButlerState: OHUser: DANDate: 01-15-94

Subtitle: Culvert StudyChecked: _____Date: _____

Subarea : 5

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			
OTHER AGRICULTURAL LANDS				
Brush - brush, weed, grass mix good	-	.07(48)	-	-

Total Area (by Hydrologic Soil Group)

.07

====

SUBAREA: 5TOTAL DRAINAGE AREA: .07 Sq milesWEIGHTED CURVE NUMBER:48

Project : GENEVA ACCESS

County : Butler

State: OH

User: DAN

Checked: _____

Date: 01-15-94

Subtitle: Culvert Study

Subarea : 6

Date: _____

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			

OTHER AGRICULTURAL LANDS				
Brush - brush, weed, grass mix good	-	.04(48)	-	-

Total Area (by Hydrologic Soil Group)

.04

====

SUBAREA: 6 TOTAL DRAINAGE AREA: .04 Sq miles WEIGHTED CURVE NUMBER:48

Project : GENEVA ACCESS

County : Butler

State: OH

User: DAN

Checked: _____

Date: 01-15-94

Subtitle: Culvert Study

Subarea : 7

Date: _____

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			

FULLY DEVELOPED URBAN AREAS (Veg Estab.)				
Open space (Lawns,parks etc.)				
Good condition; grass cover > 75%	-	.02(61)	-	-
Impervious Areas				
Paved parking lots, roofs, driveways	-	.02(98)	-	-
OTHER AGRICULTURAL LANDS				
Brush - brush, weed, grass mix good	-	.02(48)	-	-
Total Area (by Hydrologic Soil Group)		.06		
		====		

SUBAREA: 7

TOTAL DRAINAGE AREA: .06 Sq miles

WEIGHTED CURVE NUMBER:69

ct : GENEVA ACCESS

County : Butler

Subtitle: Culvert Study

Subarea : 8

User: DAN

State: OH

Checked: _____

Date: 01-15-94

Date: _____

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			

FULLY DEVELOPED URBAN AREAS (Veg Estab.)				
Urban Districts	Avg % imperv			
Industrial	72	-	.09(88)	-

Total Area (by Hydrologic Soil Group)

.09

====

SUBAREA: 8 TOTAL DRAINAGE AREA: .09 Sq miles WEIGHTED CURVE NUMBER:88

Project : GENEVA ACCESS

County : Butler

State: OH

User: DAN

Checked: _____

Date: 01-15-94

Subtitle: Culvert Study

Date: _____

Subarea : 9

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
	Sq miles (CN)			

FULLY DEVELOPED URBAN AREAS (Veg Estab.)				
Open space (Lawns,parks etc.)				
Good condition; grass cover > 75%	-	.015(61)	-	-
OTHER AGRICULTURAL LANDS				
Brush - brush, weed, grass mix good	-	.055(48)	-	-
Total Area (by Hydrologic Soil Group)		.07		
		====		

SUBAREA: 9

TOTAL DRAINAGE AREA: .07 Sq miles

WEIGHTED CURVE NUMBER:51

ct : GENEVA ACCESS

County : Butler

State: OH

User: DAN

Checked: _____

Date: 01-15-94

Subtitle: Culvert Study

Date: _____

Subarea : 10

COVER DESCRIPTION	Hydrologic Soil Group			
	A	B	C	D
Sq miles (CN)				

FULLY DEVELOPED URBAN AREAS (Veg Estab.)				
Open space (Lawns,parks etc.)				
Fair condition; grass cover 50% to 75%	-	.005(69)	-	-
Streets and roads				
Paved; curbs and storm sewers	-	.005(98)	-	-
OTHER AGRICULTURAL LANDS				
Brush - brush, weed, grass mix fair	-	.02(56)	-	-
Total Area (by Hydrologic Soil Group)		.03		
		====		

SUBAREA: 10 TOTAL DRAINAGE AREA: .03 Sq miles WEIGHTED CURVE NUMBER:65

User DANz

>>>> Identification Data <<<<

Date 01-15-94

Project GENEVA ACCESS

County Butler

State OH

Subtitle Culvert Study

>>>> Subarea Selection and Summary <<<<

Area Units (Acres,SqMi,Percent) S	Subareas	Accum. Sq miles	Weighted CN
Select appropriate Area	# 1 1zzzzz	0.130	55
Units (A,S, or P above).	# 2 2zzzzz	0.070	48
Then place cursor on line	# 3 3zzzzz	0.120	70
for desired subarea. Key	# 4 4zzzzz	0.040	92
in name, if blank, and	# 5 5zzzzz	0.070	48
press PgDn to bring up	# 6 6zzzzz	0.040	48
first land use-CN screen.	# 7 7zzzzz	0.060	69
Use PgUp and PgDn to	# 8 8zzzzz	0.090	88
loop through the land uses	# 9 9zzzzz	0.070	51
and F8 to return here.	#10 10zzzz z	0.030	65

0.62

0.72

F1Help F2Print F3Load F4Save F5DOS F6Zero

Location : GENEVA ACCESS User: DAN Date: 01-15-94
County : Butler State: OH Checked: Date:
Subtitle: Culvert Study

----- Subarea #1 - 1 -----									
Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.10	i					0.831
Shallow Concent'd		1000	.10	u					0.054
Open Channel		1000	.04			.08 48	24		0.047
Time of Concentration = 0.93*									
=====									

----- Subarea #2 - 2 -----									
Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.017	f					0.644
Shallow Concent'd		1100	.014	u					0.160
Time of Concentration = 0.80*									
=====									

----- Subarea #3 - 3 -----									
Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.04	e					0.297
Shallow Concent'd		300	.033	u					0.028
Shallow Concent'd		300	.033	p					0.023
Open Channel		1000	.025			.08 2	1		0.059
Time of Concentration = 0.41*									
=====									
Open Channel		1000	.025			.08 2	1		0.059
Travel Time = 0.06*									
=====									

* - Generated for use by TABULAR method

State : GENEVA ACCESS User: DAN Date: 01-15-94
 County : Butler State: OH Checked: ____ Date: ____
 Subtitle: Culvert Study

----- Subarea #4 - 4 -----

Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
-----------	----------------	----------------	------------------	-----------------	---	-----------------	------------	----------------------	--------------

ct : GENEVA ACCESS User: DAN Date: 01-15-94
County : Butler State: OH Checked: Date:
Subtitle: Culvert Study

----- Subarea #8 - 8 -----									
Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	200	.05	f					0.303
Shallow Concent'd		1000	.05	p					0.061
Open Channel		1500	.02		.08 2		1		0.100
Time of Concentration = 0.46*									
=====									
Open Channel		1500	.02		.08 2		1		0.100
Travel Time = 0.10*									
=====									

----- Subarea #9 - 9 -----									
Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.033	e					0.321
Shallow Concent'd		800	.005	u					0.195
Open Channel		2700	.0003		.08 2		1		1.465
Time of Concentration = 1.98*									
=====									

----- Subarea #10 - 10 -----									
Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.1	i					0.831
Shallow Concent'd		800	.075	p					0.040
Open Channel		600	.0083		.08 2		1		0.062
Time of Concentration = 0.93*									
=====									
Open Channel		600	.0083		.08 2		1		0.062
Travel Time = 0.06*									
=====									

--- Sheet Flow Surface Codes ---
A Smooth Surface F Grass, Dense --- Shallow Concentrated ---
B Fallow (No Res.) G Grass, Bermuda --- Surface Codes ---
C Cultivated < 20 % Res. H Woods, Light P Paved
D Cultivated > 20 % Res. I Woods, Dense U Unpaved
E Grass-Range, Short

GENEVA ACCESS Butler,OH DAN 01-15-94
Culvert Study

>>>> Subarea Data <<<<

Subarea Name	Drainage Area (sq mi)	Runoff Curve Number	Time of Concen- tration (hrs)	Travel Thru Subarea (hrs)	Downstream Subarea Name	24-Hour Rain (in)
1zzzzz	.13zz *	55 *	.93z *	zzzz	4zzzzz	4.8z
2zzzzz	.07zz *	48 *	.8zz *	zzzz	3zzzzz	4.8z
3zzzzz	.12zz *	70 *	.41z *	.06z *	8zzzzz	4.8z
4zzzzz	.04zz *	92 *	.3zz *	.03z *	5zzzzz	4.8z
5zzzzz	.07zz *	48 *	.71z *	.18z *	zzzzzz	4.8z
6zzzzz	.04zz *	48 *	.28z *	zzzz	7zzzzz	4.8z
7zzzzz	.06zz *	69 *	.57z *	.09z *	8zzzzz	4.8z
8zzzzz	.09zz *	88 *	.46z *	.1zz *	zzzzzz	4.8z
9zzzzz	.07zz *	51 *	1.98 *	zzzz	zzzzzz	4.8z
10zzzz	.03zz *	65 *	.93z *	.06z *	zzzzzz	4.8z z

F1Help F2Print F3Load F4Save F5DOS F6Zero F7Compute F9RCN F10TCTT

User DAN

>>>> Identification Data <<<<

Date 01-19-94

Project GENEVA ACCESS

County Butler

State OH

Subtitle Culvert Study at Access to Property

>>>> Basic Watershed Data <<<<

Rainfall-Type (I,IA,II,III)

II

Rainfall Frequency 25

years

If constant rainfall over entire watershed, 24-Hour Rain 4.8 in.

(If rainfall varies by subarea enter on next screen.)

Interpolate hydrograph tables based on Ia/P ratio Y

(Enter Y for yes and N for no)

Z

F1Help

F2Print

F3Load

F4Save

F5DOS

F6Zero

F7Compute

F9RCN

F10TCTT

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

Subarea	Time									
	11.9	12.0	12.1	12.2	12.3	12.4	12.5	12.6	12.7	12.8
1	0	0	0	0	1	2	5	9	14	19
2	0	0	0	0	0	1	2	3	5	6
3	9	16	32	60	92	112	106	88	67	51
4	8	13	24	45	74	91	84	66	48	35
5	0	0	0	0	1	3	5	7	8	8
6	0	0	0	1	3	5	6	6	5	4
7	3	5	9	17	30	41	48	46	40	32
8	18	29	53	96	146	166	159	126	93	71
9	0	0	0	0	0	0	1	1	2	2
10	1	1	1	2	3	5	8	11	13	14
TOTAL	39	64	119	221	350	426	424	363	295	242

Esc exit compute process

t i m e

l a t e r

y e a r

D i s p l a y

TOTAL DISCHARGE TO "C"

(IS BY WAY OF "E" & "F")

1/20/94
Culvert calc.
Sht. 1 of 4

"G" "E" "D" "B" "A"


GENEVA ACCESS Comparison of Existing Culverts
Assume all flowing full, both ends submerged, $H = \Delta$ Surface elevations, ft.
 $K_e = \text{Entry loss coeff.}$
 $n = \text{roughness coeff.}$
 $L = \text{Length of culvert, ft.}$
 $R = \frac{A_p}{P} = \text{flow cross-section}$
 $Flow Q = A V = Area \times Vel. = cfs.$ wetted perimeter, ft.

$$V = \sqrt{\frac{H}{\frac{(1 + K_e)}{2g} + \frac{n^2 L}{2.21 R^{4/3}}}}$$

Culvert	H	A	P	R	1+K _e	$\frac{1+K_e}{2g}$	n	L	R ^{4/3}	$\frac{n^2 L}{2.21 R^{4/3}}$	V ²	Q	REMARKS	
"G"	1.5	2(12.6)	2(12.6)	1.0	1.50	0.023	.024	40	1.	0.010	45.5	6.75	170.	See Sht. 3
"E"	1.5	2(29.4)	2(22.4)	1.31	1.50	0.023	.013	20	1.43	0.001	62.5	7.91	465.	clogged @ 1' over soffit. 25% flow
"D"	1.5	2(29.4)	2(22.4)	1.31	1.50	0.023	.013	40	1.43	0.002	60.0	7.75	455.	clogged @ 1' over soffit. 25% flow
"B"	1.5	32.4	25.4	1.28	1.50	0.023	.025	10	1.39	0.002	60.0	7.75	251.	debris @ 1' over soffit.
"A"	1.5	76.8	36.8	2.09	1.50	0.023	.013	60	2.67	0.002	60.0	7.75	595.	new amount clean
											add'l areas contribution		100.4	
													495	

GENEVA ACCESS.

What general water surface slope would accommodate a flow of 436 cfs in an earthen channel of the following approx. configuration?



Trial	Depth	A	p.	R.	n	V	R ^{7/3}	V ³	S
	5'	125	41.8	3.0	0.05	3.4	2.08	.0549	0.003
	5'				0.04			.0439	0.002
	5'				0.03			.0329	0.001
	4.5'	106	38.6	2.75	0.05	4.02	1.96	.0688	0.005
	4.5'				0.04			.0550	0.003
	4.5'				0.03			.0413	0.002

$$V = \frac{(1.49) R^{2/3} S^{1/2}}{n}$$

$$\sqrt{S} = \frac{nV}{(1.49) R^{2/3}}$$

(Since pipe flow velocities are $\sim \sqrt{H}$, capacities calculated on sht. 1 can be reworked by $\sqrt{\frac{1.1}{1.5}} = 1.67 = 0.82 \times \text{calc. values}$
 ("G" head is not involved) "E" $\div$ "D" $\div$ 460 cfs.
 * 0.82
 377 cfs. probable exemplary culvert flow.

1/20/94
 Culvert Calcs.
 Sht. 2 of 4

Comment

The general slope of the stream bed was determined by survey (see Exhibit) to be approx - 0.0042. If stream flow demand is - 0.0020

Balance avail.

for head losses = 0.0022

Length of Waterway = 2100. ft.

Head avail. for

5 culverts = 4.62 ft.


Avail. available

per culvert = 0.92

say 1. ft.

1/20/74
 Culvert calcs.
 Sht. 3 of 4

Culvert "F", STONE CULVERT UNDER B & O RR.
 Embankment



Washout of ballast and ties indicates that in recent hydrologic time the spur track was topped. Since the track is nearly level, culvert capacity at moment of topping was as per calc. on Sht. E-1 = 170 cfs.

Flow thru "F":
 Practically pipe flow, but reduce to $H_{above} = (1 + K_e) \frac{V^2}{2g}$

$\pm K_e = 0.5,$
 $r = 6.5 \sqrt{H}$


H	N	F	Q
1.2	7.1	22.2	158 cfs
2.2	9.6		214
3.2	11.6		258
4.2	13.3		296

Range of max. expectations based on ponding upstream of B & O (c & o) RR culvert

1/20/94

Sie TABULAR HYDROGRAPHIC EXHIBITS

Max. discharge expected at culvert location = 426 cfs.



max. upstream elev. = use $657.5 - (350 \times 0.002) = 656.8$
 min downstream elev. = use Orchem soffit plus 1 ft. plus (1400×0.002)
 $= 651.1 + 1.00 + 2.80 = 654.8$

avg. base el. = 650.7

(not flowing full except just inside entry, entrance shape to reduce $K_e = 0.3$)

rough estimate, $V = \sqrt{\frac{2gH}{1 + K_e}} = \sqrt{\frac{(64.4)(2)}{1.3}} = \sqrt{99} = 9.95 \text{ fps}$, a little high, $\Delta H = 2'$

Reducing vel. to a lesser value; $V = \sqrt{\frac{1.5}{2} \times 9.95} = 8.6 \text{ fps}$.

Area req'd = $\frac{426}{8.6} = 49.5 \text{ ft}^2$ @ 4.6' of flow

Dimeso 10'-2" x 6'-11" - 5' x 1' - Pipe Arch should about meet this reqmt (equiv $\phi = 9'-0" \phi$)


Have possibility of setting across road elev, w/ 27' of cover?

650.7	Road surface
7.0 rise	
2.25 cover	
659.95 ± 31.	

Barely ok -

Max. grade up to $\pm$ arch from $\pm$ intersec'n = 4%
 $.04 \times 40' = 1.60'$
 $\frac{658.3}{659.9}$

Put culvert pipe on a slope of 0.0042




11-80



ENLARGEMENT OF U.S.G.S. 1987 PHOTO REVISION
OF 1984 SURFACE FEATURES
GLENDALE, OHIO QUADRANGLE

APPROX. SCALE 1" = 1000'



Project : geneva bldg, drives genevabb
 County : butler State: oh
 Subtitle:

User: dan Date: 01-31-94
 Checked: ____ Date: ____

Total watershed area: 0.005 sq mi Rainfall type: II Frequency: 25 years

----- Subareas -----
 bldg drives lawn
 Area(sq mi) 0.00* 0.00* 0.00*
 Rainfall(in) 4.8 4.8 4.8
 Curve number 98* 98* 69*
 Runoff(in) 4.56 4.56 1.81

TR-55 TABULAR HYDROGRAPH METHOD

VERSION 1.11

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

Subarea	Time									
	11.0	11.3	11.6	11.9	12.0	12.1	12.2	12.3	12.4	12.5
bldg	0	0	0	3	6	9	6	2	1	1
drives	0	0	0	3	6	9	6	2	1	1
lawn	0	0	0	0	1	1	1	1	0	0

TOTAL 0 0 0 6 13 19 13 5 2 2

Esc exit compute process

i s p l a y
 t i m e
 l a t e r t i m e

e a r l i e r
 D i s p l a y

File GENEVABB

Project : GENEVA ACCESS
 County : Butler
 Subtitle: Culvert Study

GENEVA 2C

User: DAN
 State: OH
 Checked: _____

Date: 01-19-94
 Date: _____

Total watershed area: 0.720 sq mi Rainfall type: II Frequency: 25 years

	Subareas				
	1	2	3	4	5
Area(sq mi)	0.13*	0.07*	0.12*	0.04*	0.07*
Rainfall(in)	4.8	4.8	4.8	4.8	4.8
		48*	70*	92*	48*

TR-55 TABULAR HYDROGRAPH METHOD

VERSION 1.11

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

Subarea	Time									
	11.9	12.0	12.1	12.2	12.3	12.4	12.5	12.6	12.7	12.8
1	0	0	0	0	1	2	5	9	14	19
2	0	0	0	0	0	1	2	3	5	6
3	9	16	32	60	92	112	106	88	67	51
4	8	13	24	45	74	91	84	66	48	35
5	0	0	0	0	1	3	5	7	8	8
6	0	0	0	1	3	5	6	6	5	4
7	3	5	9	17	30	41	48	46	40	32
8	18	29	53	96	146	166	159	126	93	71
9	0	0	0	0	0	0	1	1	2	2
10	1	1	1	2	3	5	8	11	13	14
TOTAL	39	64	119	221	350	426	424	363	295	242

File GENEVA 2C

Esc exit compute process i s p l a y e a r l i e r
 t i m e D i s p l a y
 l a t e r t i m e

Project : GENEVA ACCESS
 County : Butler
 Subtitle: Culvert Study

User: DAN
 State: OH
 Checked: _____
 Date: 01-19-94
 Date: _____

----- Subarea #8 - 8 -----

Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	200	.05	f					0.303
Shallow Concent'd		1000	.05	p					0.061
Open Channel		1500	.02		.08 2		1		0.100
									Time of Concentration = 0.46*
									=====

Open Channel		1500	.02		.08 2		1		0.100
									Travel Time = 0.10*
									=====

----- Subarea #9 - 9 -----

Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.033	e					0.321
Shallow Concent'd		800	.005	u					0.195
Open Channel		2700	.0003		.08 2		1		1.465
									Time of Concentration = 1.98*
									=====

----- Subarea #10 - 10 -----

Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet	2.88	300	.1	i					0.831
Shallow Concent'd		800	.075	p					0.040
Open Channel		600	.0083		.08 2		1		0.062
									Time of Concentration = 0.93*
									=====
Open Channel		600	.0083		.08 2		1		0.062
									Travel Time = 0.06*
									=====

--- Sheet Flow Surface Codes ---

A Smooth Surface	F Grass, Dense	--- Shallow Concentrated ---
B Fallow (No Res.)	G Grass, Bermuda	--- Surface Codes ---
C Cultivated < 20 % Res.	H Woods, Light	P Paved
D Cultivated > 20 % Res.	I Woods, Dense	U Unpaved
E Grass-Range, Short		

Project : geneva bldg site rich genevabs User: dan Date: 01-31-94
County : butler State: oh Checked: _____ Date: _____
Subtitle: compare site runoff time to calculated hydrograph of geneva 2c

Total watershed area: 0.005 sq mi Rainfall type: II Frequency: 25 years

----- Subareas -----

hill
Area(sq mi) 0.00*
Rainfall(in) 4.8
Curve number 57*
Runoff(in) 1.00

TR-55 TABULAR HYDROGRAPH METHOD

VERSION 1.11

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

Subarea	11.9	12.0	12.1	12.2	12.3	12.4	12.5	12.6	12.7	12.8
hill	0	0	0	1	1	2	2	2	1	1

File GENEVABS

Project : geneva bldg site dich genevabs User: dan Date: 01-31-94
 County : butler State: oh Checked: _____ Date: _____
 Subtitle: compare site runoff time to calculated hydrograph of geneva 2c

```


----- Subarea #1 - hill -----
Flow Type  2 year  Length  Slope  Surface  n  Area  Wp  Velocity  Time
           rain    (ft)   (ft/ft)  code      (sq/ft) (ft) (ft/sec) (hr)
-----
Sheet      2.88    75      0.13    i                0.247
Sheet      130     0.06    h                0.300
Shallow Concent'd  175     0.03    u                0.017
                                           Time of Concentration = 0.56*
                                           =====
  
```

--- Sheet Flow Surface Codes ---

A Smooth Surface	F Grass, Dense	--- Shallow Concentrated ---
B Fallow (No Res.)	G Grass, Burmuda	--- Surface Codes ---
C Cultivated < 20 % Res.	H Woods, Light	P Paved
D Cultivated > 20 % Res.	I Woods, Dense	U Unpaved
E Grass-Range, Short		


* - Generated for use by TABULAR method

EXHIBIT A.
PROPERTY LOCATION



LANDS OF THE DE
SCALE: 1"=400'

1980-81



Scale - 1" = 180' ±

GENEVA 2/10/94

TR-55 TABULAR DISCHARGE METHOD

VERSION 1.11

Project : geneva bldg, drives genevabb User: dan Date: 01-31-94
 County : butler State: oh Checked: ____ Date: ____
 Subtitle:

Total watershed area: 0.005 sq mi Rainfall type: II Frequency: 25 years

	Subareas		
	bldg	drives	lawn
Area(sq mi)	0.00*	0.00*	0.00*
Rainfall(in)	4.8	4.8	4.8
Curve number	98*	98*	69*
Runoff(in)	4.56	4.56	1.81

TR-55 TABULAR HYDROGRAPH METHOD

VERSION 1.11

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

Subarea	Time									
	11.0	11.3	11.6	11.9	12.0	12.1	12.2	12.3	12.4	12.5
bldg	0	0	0	3	6	9	6	2	1	1
drives	0	0	0	3	6	9	6	2	1	1
lawn	0	0	0	0	1	1	1	1	0	0

TOTAL 0 0 0 6 13 19 13 5 2 2

Esc exit compute process i s p l a y e
 t i m e D
 l a t e r t i m e

File GENEVABB

a r l i e r
 i s p l a y

Project : GENEVA ACCESS
 County : Butler
 Subtitle: Culvert Study

GENEVA 2C

User: DAN
 State: OH
 Checked: _____

Date: 01-19-94
 Date: _____

Total watershed area: 0.720 sq mi Rainfall type: II Frequency: 25 years

	Subareas				
	1	2	3	4	5
Area(sq mi)	0.13*	0.07*	0.12*	0.04*	0.07*
Rainfall(in)	4.8	4.8	4.8	4.8	4.8
		48*	70*	92*	48*

TR-55 TABULAR HYDROGRAPH METHOD

VERSION 1.11

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

Subarea	Time									
	11.9	12.0	12.1	12.2	12.3	12.4	12.5	12.6	12.7	12.8
1	0	0	0	0	1	2	5	9	14	19
2	0	0	0	0	0	1	2	3	5	6
3	9	16	32	60	92	112	106	88	67	51
4	8	13	24	45	74	91	84	66	48	35
5	0	0	0	0	1	3	5	7	8	8
6	0	0	0	1	3	5	6	6	5	4
7	3	5	9	17	30	41	48	46	40	32
8	18	29	53	96	146	166	159	126	93	71
9	0	0	0	0	0	0	1	1	2	2
10	1	1	1	2	3	5	8	11	13	14
TOTAL	39	64	119	221	350	426	424	363	295	242

File GENEVA 2C

Esc exit compute process i s p l a y e a r l i e r
 t i m e D i s p l a y
 l a t e r t i m e

Project : GENEVA ACCESS
 County : Butler
 Subtitle: Culvert Study

User: DAN
 State: OH
 Checked: _____

Date: 01-19-94
 Date: _____

```

----- Subarea #8 - 8 -----
Flow Type  2 year  Length  Slope  Surface  n  Area  Wp  Velocity  Time
           rain    (ft)   (ft/ft) code    (sq/ft) (ft) (ft/sec) (hr)
-----
Sheet      2.88    200    .05    f                0.303
Shallow Concent'd  1000    .05    p                0.061
Open Channel  1500    .02                .08 2    1    0.100
                                           Time of Concentration = 0.46*
                                           =====
  
```

```

Open Channel  1500    .02                .08 2    1    0.100
                                           Travel Time = 0.10*
                                           =====
  
```

```

----- Subarea #9 - 9 -----
Flow Type  2 year  Length  Slope  Surface  n  Area  Wp  Velocity  Time
           rain    (ft)   (ft/ft) code    (sq/ft) (ft) (ft/sec) (hr)
-----
Sheet      2.88    300    .033   e                0.321
Shallow Concent'd  800    .005   u                0.195
Open Channel  2700    .0003    .08 2    1    1.465
                                           Time of Concentration = 1.98*
                                           =====
  
```

```

----- Subarea #10 - 10 -----
Flow Type  2 year  Length  Slope  Surface  n  Area  Wp  Velocity  Time
           rain    (ft)   (ft/ft) code    (sq/ft) (ft) (ft/sec) (hr)
-----
Sheet      2.88    300    .1     i                0.831
Shallow Concent'd  800    .075   p                0.040
Open Channel  600    .0083    .08 2    1    0.062
                                           Time of Concentration = 0.93*
                                           =====
  
```

```

Open Channel  600    .0083    .08 2    1    0.062
                                           Travel Time = 0.06*
                                           =====
  
```

--- Sheet Flow Surface Codes ---

A Smooth Surface
 B Fallow (No Res.)
 C Cultivated < 20 % Res.
 D Cultivated > 20 % Res.
 E Grass-Range, Short

F Grass, Dense
 G Grass, Burmuda
 H Woods, Light
 I Woods, Dense

--- Shallow Concentrated ---
 --- Surface Codes ---
 P Paved
 U Unpaved

Project : geneva bldg site nich genevabs User: dan Date: 01-31-94
 County : butler State: oh Checked: _____ Date: _____
 Subtitle: compare site runoff time to calculated hydrograph of geneva 2c

Total watershed area: 0.005 sq mi Rainfall type: II Frequency: 25 years
 ----- Subareas -----

hill
 Area(sq mi) 0.00*
 Rainfall(in) 4.8
 Curve number 57*
 Runoff(in) 1.00

TR-55 TABULAR HYDROGRAPH METHOD

VERSION 1.11

SUBAREA CONTRIBUTIONS AND TOTAL DISCHARGE (CFS) AT OUTLET

	-----Time-----									
Subarea	11.9	12.0	12.1	12.2	12.3	12.4	12.5	12.6	12.7	12.8
hill	0	0	0	1	1	2	2	2	1	1

File GENEVABS

Project : geneva bldg site dich genevabs User: dan Date: 01-31-94
 County : butler State: oh Checked: _____ Date: _____
 Subtitle: compare site runoff time to calculated hydrograph of geneva 2c

```

----- Subarea #1 - hill -----
Flow Type  2 year  Length  Slope Surface  n  Area  Wp  Velocity  Time
            rain    (ft)   (ft/ft)  code   (sq/ft) (ft) (ft/sec) (hr)
-----
Sheet      2.88    75      0.13    i                      0.247
Sheet                      130    0.06    h                      0.300
Shallow Concent'd  175    0.03    u                      0.017

```


Time of Concentration = 0.56*

=====

--- Sheet Flow Surface Codes ---

A Smooth Surface	F Grass, Dense	--- Shallow Concentrated ---
B Fallow (No Res.)	G Grass, Bermuda	--- Surface Codes ---
C Cultivated < 20 % Res.	H Woods, Light	P Paved
D Cultivated > 20 % Res.	I Woods, Dense	U Unpaved
E Grass-Range, Short		


* - Generated for use by TABULAR method



LANDS OF THE DE
SCALE: 1"=400'


1980-81

EXHIBIT A.
PROPERTY LOCATION



Scale - 1" = 180' ±
GENEVA 2/10/94

SITES	BEFORE CONSTRUCTION	AFTER CONSTRUCTION	Subarea		Drain		Drain		Slope		Geneva building site Miscellaneous (GENEVA BS)
			Area	Dist.	Area	Dist.	Area	Dist.	Area	Dist.	
{	Rice ①		450x60	0.6	Ward, govt	0.13	{	As proposed: hds, drivs, lawn (GENEVA BB)			
	Slopes ②		450x125	1.3	Wd. & Brush, govt	0.06					
	Flatter ③		450x140	1.4	Lance grass	0.03					
	Bldg ①	53000 #	1.2	Imperv. { Roof 14"/ft. } piping							
	Drivew ②	53000 #	1.2	Imperv. { 0.03 slopes } lawn, Fair { 0.03 slopes }							
	Lawns ③	(bal.)	0.7								



TRSS Summary of storm runoff, 25 year storm Type II Rainfall:

Peak discharge at culvert site from upstream
 File GENEVA 2C
 Add Redevelopment site dischg. File GENEVA BS totals

Repeat File GENEVA 2C
 Add Redevelopment site dischg. File GENEVA BS totals

Conclusion: No REENTRANT NECESSARY.
 Peak discharge is not increased.

