



**NOTE 1**  
 CONTRACTOR SHALL BE ADVISED THAT THE VARIABLE DEPTH INTERMEDIATE COURSE SHALL BE FIELD ADJUSTED AS DIRECTED BY THE ENGINEER'S OFFICE. THE INTENT OF THE VARIABLE DEPTH INTERMEDIATE COURSE IS TO REESTABLISH A ROADWAY CROWN AND CROSS SLOPE. PROPOSED CROSS SLOPE SHALL BE A MINIMUM 1/4" PER FOOT. THIS WORK SHALL BE PERFORMED AT THE DIRECTION OF THE BUTLER COUNTY ENGINEER'S OFFICE.

END AREA		VOLUME	
CUT	FILL	CUT	FILL
34	0	0	0

SHEET TOTAL	212	0
-------------	-----	---

**KLEINGERS & ASSOCIATES**  
 ENGINEERS AND SURVEYORS  
 6365 Centre Park Drive  
 West Chester, OH 45069  
 513-779-7851 Fax: 513-779-7852

**CROSS SECTIONS - BETHANY ROAD  
 STA.18+25 TO STA. 19+00**

CALCULATED GAU  
 CHECKED NMM

VERTICAL SCALE IN FEET  
 HORIZONTAL SCALE IN FEET