



NOTE 1
 CONTRACTOR SHALL BE ADVISED THAT THE VARIABLE DEPTH INTERMEDIATE COURSE SHALL BE FIELD ADJUSTED AS DIRECTED BY THE ENGINEER'S OFFICE. THE INTENT OF THE VARIABLE DEPTH INTERMEDIATE COURSE IS TO REESTABLISH A ROADWAY-CROWN AND CROSS SLOPE. PROPOSED CROSS SLOPE SHALL BE A MINIMUM 1/8" PER FOOT. THIS WORK SHALL BE PERFORMED AT THE DIRECTION OF THE BUTLER COUNTY ENGINEER'S OFFICE.

END AREA	CUT	FILL	CUT	FILL	VOLUME
4.6	18.6	0	4	13	
4.3	13.3	0	1	4	
2.6	2.4	0	1	1	
0.5	2.1	0	0	0	
0.2	0.9	0	0	0	

SHEET TOTAL	10	35
-------------	----	----

CALCULATED GAU
 CHECKED NMM
 VERTICAL SCALE IN FEET
 HORIZONTAL SCALE IN FEET

**CROSS SECTIONS - BETHANY ROAD
 STA.12+67.01 TO STA. 13+75**

